

# Correlation of SARS-CoV-2 in Wastewater and Individual Testing Results in a Jail, Atlanta, Georgia, USA

Lindsay B. Saber, Shanika S. Kennedy, Yixin Yang, Kyler N. Moore, Yuke Wang, Stephen P. Hilton, Tylis Y. Chang, Pengbo Liu, Victoria L. Phillips, Matthew J. Akiyama, Christine L. Moe, Anne C. Spaulding

Institution-level wastewater-based surveillance was implemented during the COVID-19 pandemic, including in carceral facilities. We examined the relationship between COVID-19 diagnostic test results of residents in a jail in Atlanta, Georgia, USA (average population  $\approx$ 2,700), and quantitative reverse transcription PCR signal for SARS-CoV-2 in weekly wastewater samples collected during October 2021–May 2022. The jail offered residents rapid antigen testing at entry and periodic mass screenings by reverse transcription PCR of self-collected nasal swab specimens. We aggregated individual test data, calculated the Spearman correlation coefficient, and performed logistic regression to examine the relationship between strength of SARS-CoV-2 PCR signal (cycle threshold value) in wastewater and percentage of jail population that tested positive for COVID-19. Of 13,745 nasal specimens collected, 3.9% were COVID-positive (range 0%–29.5% per week). We observed a strong inverse correlation between diagnostic test positivity and cycle threshold value ( $r = -0.67$ ;  $p < 0.01$ ). Wastewater-based surveillance represents an effective strategy for jailwide surveillance of COVID-19.

Jails, which are short-term carceral institutions, experienced numerous factors during the COVID-19 pandemic that can lead to SARS-CoV-2 transmission, including crowding, mask shortages, and difficulty implementing sufficient quarantine and isolation practices (1,2). In 2020, 7% of US jails were operating over capacity, despite total admissions decreasing

from 10.3 million in 2019 to 8.7 million in 2020 (16%) (3). Although the Centers for Disease Control and Prevention published guidelines for COVID-19 management in carceral settings (4), COVID-19 incidence exceeded that of surrounding communities up to 5-fold (5–7). In addition, there are logistical challenges to regularly screening jail residents for asymptomatic disease, especially in large jails that house thousands of persons (5,8–12).

Wastewater-based surveillance (WBS) might detect SARS-CoV-2 before onset of clinical symptoms and could serve as a sensitive, noninvasive early warning tool both regionally and at an institutional level (13–19). WBS might also limit biases that arise from residents avoiding testing or medical care. If implemented in jails, WBS could potentially save time, resources, and lives. This study examined WBS for monitoring SARS-CoV-2 infection in a large jail in Atlanta, Georgia, USA.


## Methods

### Setting and Population

The Emory University Institutional Review Board determined that this study constituted non-human subject research. The study was set in the Fulton County (Georgia) Jail, which has a 2,600-person capacity (20). The mean  $\pm$  SD population during our study period, October 20, 2021–May 4, 2022, was  $2,700 \pm 133$  persons. The main complex has north and south towers, each with 7 floors, and 6 housing units per floor. People entering move into housing units within 24 hours, predominantly to 1 designated floor of the south tower. Housing units typically hold 40 persons maximum, in 20 two-person cells. When volume exceeds capacity, residents sleep

Author affiliations: Emory University, Atlanta, Georgia, USA (L.B. Saber, S.S. Kennedy, Y. Yang, K.N. Moore, Y. Wang, S.P. Hilton, P. Liu, V.L. Phillips, C.L. Moe, A.C. Spaulding); Zucker School of Medicine at Hofstra/Northwell, Hempstead, New York, USA (T.Y. Chang); Albert Einstein College of Medicine, Bronx, New York, USA (M.J. Akiyama)

DOI: <https://doi.org/10.3201/eid2813.230775>



**Figure 1.** Moore swab: 4-in by 4-in cotton gauze squares tied together with nylon fishing line (21).

on mattresses on the floor. The population of this study was jail residents, who on average outnumber correctional officers 15-fold.

### Wastewater Monitoring


A sampling team from Emory University in Atlanta collected weekly wastewater samples from the jail throughout the project period. Moore swabs (Figure 1) were suspended overnight in manhole sites around the jail property (Figure 2) (21,22). Eluted wastewater from the swabs was tested by using quantitative real-time reverse transcription PCR (qRT-PCR) at the Center for Global Safe Water, Sanitation, and Hygiene Laboratory at Emory University, as described (21,23). The amount of SARS-CoV-2 viral RNA present in a sample was measured by qRT-PCR cycle threshold (Ct) value, which is inversely related to the concentration of SARS-CoV-2 in the Moore swab eluate. Positive samples were defined as those with qRT-PCR results in both duplicate wells  $\leq 40$  Ct and within 2 Ct of each other. For this analysis, wastewater data originated from a single, downstream collection point, site 3 (Figure 2), which contained a mixture of wastewater from the south and north towers (Appendix, <https://wwwnc.cdc.gov/EID/article/29/13/23-0775-App1.pdf>). We used those data as proxy for wastewater concentration of SARS-CoV-2 for the entire jail. Samples were not collected during 3 holiday weeks in November–December 2021.

### COVID-19 Individual Diagnostic Testing


Healthcare staff routinely offered residents opt-out, rapid antigen testing at intake, as part of the jail's entry protocol (BinaxNOW, Abbott Laboratories, <https://www.abbott.com>, through January 31, 2022; QuickVue; Quidel Corporation, <https://www.quidel>.

com, starting February 1, 2022). After intake, antigen testing was available if residents exhibited COVID-19 symptoms, or upon request.

An Emory University team offered opt-out mass screening to a subset of jail residents on a weekly basis. Residents opting in provided self-collected nasal specimens, which were tested by RT-PCR. Insufficient staffing precluded offering mass screening to the entire resident population at any single timepoint. Each week, areas of the jail screened by RT-PCR were either randomly selected or targeted on the basis of known ongoing outbreaks.



**Figure 2.** Outline of the Fulton County Jail, Atlanta, Georgia, USA, showing wastewater-based surveillance collection sites. Site 3 was used for final analysis as a proxy for wastewater-based surveillance results of the entire jail.



**Figure 3.** Average Ct values of wastewater samples (black lines) versus total percentage of negative COVID-19 diagnostic test results (red lines), Fulton County Jail, Atlanta, Georgia, USA, October 2021–May 2022. Dot sizes are proportional to the percentage of the jail population undergoing a COVID-19 diagnostic test for the corresponding week. Ct, cycle threshold.

### Data Analysis

We stored, managed, and analyzed all data in Excel software (Microsoft, <https://www.microsoft.com>) and R software (The R Foundation for Statistical Computing, <https://www.r-project.org>). We aggregated the PCR data with results of intake antigen testing to calculate the percentage of diagnostic tests with positive results at each timepoint. First, we analyzed diagnostic test results and wastewater RT-PCR results separately to examine temporal trends. We then compared those trends through time-matched results from the COVID-19 diagnostic tests and WBS. We calculated the Spearman correlation coefficient ( $r$ ) for the relationship between Ct values of wastewater samples and percentage of the COVID-19 diagnostic tests that had positive results. Last, we performed a logistic regression analysis of the presence or absence of SARS-CoV-2 in wastewater samples and the percentage of positive COVID-19 diagnostic tests matched by week. We assigned a Ct value of 40 when the RT-PCR result for a wastewater sample was negative.

### Results

The jail population during the study period ranged from 2,497 to 2,904 residents. Most (98.4%) persons in the jail during this period were male; 88.8% were Black.

### Wastewater Monitoring


A total of 79 wastewater samples were collected from 4 manhole sites (Figure 2). Spearman correlation coefficients showed strong correlations between Ct values of wastewater samples collected from different sites on the same day (Appendix Table 2, Figure 2), confirming that results from 1 site (site 3) sufficed as a jailwide proxy.

SARS-CoV-2 was detected in 20 (80%) of 25 Moore swab samples of wastewater from site 3 during the study period. Of the 20 positive samples in the study period, the mean Ct value was 33.94 (SD 3.74).

There was considerable temporal variability in the wastewater Ct values during the study period (Figure 3). The wastewater Ct value decreased sharply between the samples collections during the week of December 15, 2021, and during the week of January 5, 2022. This decrease was followed by the lowest Ct value during the study period (28.1 on January 5, 2022, which was during the Omicron virus surge in Atlanta). The wastewater Ct values were in that range for 5 consecutive weeks of the surge (Figure 3). No SARS-CoV-2 RNA was detected in wastewater samples from 1 sampling date in November 2021 or from 4 sampling dates in March–April 2022.

### COVID-19 Diagnostic Testing

A total of 17 mass diagnostic PCR testing events resulted in 3,770 total self-collected swab specimens



**Figure 4.** PCR and rapid COVID-19 diagnostic test results, Fulton County, Jail, Atlanta, Georgia, USA, October 2021–May 2022. The percentage of the combined negative diagnostic results is overlaid, showing peak in positive results (i.e., nadir of negative results) in late December 2021.

tested by RT-PCR. A total of 9,975 rapid COVID-19 diagnostic tests were conducted at intake over 28 weeks (Table 1).

The median number of diagnostic tests conducted each week was 443 (Table 2). Most were rapid antigen tests (median = 363) rather than PCR diagnostic tests (median = 186). The weekly percentage positivity for PCR tests and for rapid antigen tests were highly correlated ( $r = 0.91$ ) (Table 3). We aggregated the PCR test and rapid antigen test results to calculate the weekly diagnostic test positivity rate during October 20, 2021–May 4, 2022. The combined test positivity averaged 3.9% (SD 6.6%) over the study period. We compiled the number of weekly COVID-19 diagnostic tests administered and the percent positivity over the study period (Figures 3, 4). The percentage positivity fluctuated but increased as the study progressed (Figure 3).

PCR tests consistently had a higher percent positivity than the routine rapid antigen tests. During the midwinter surge, there was a much higher proportion of positive PCR tests (e.g., week of December 28, 2021, 63.5%) compared with positive rapid antigen test results (24.4%). Nonetheless, the positivity rates for the PCR test and rapid antigen test were correlated

during weeks when both tests were administered ( $r = 0.65$ ;  $p = 0.004$ ).

**Wastewater and Diagnostic Comparison**

When the percent positivity for diagnostic tests was low for several weeks (e.g., March 9, 2022–April 13, 2022), the Ct values for the wastewater samples were high (38.1–40) or negative, indicating little or no detection of SARS-CoV-2 RNA in the wastewater samples. Low Ct values were measured in the wastewater samples during the weeks when the COVID-19 diagnostic test percent positivity was high (e.g., early January 2022). Overall, the total COVID-19 diagnostic test percent positivity had a strong negative correlation with the wastewater Ct values combined over time ( $r = -0.67$ ;  $p < 0.01$ ) (Table 3).

We used logistic regression to analyze the relationship between percent positivity in diagnostic testing and WBS results as a dichotomous outcome (presence/absence of SARS-CoV-2). Holding all other predictors constant, we found that the odds of a positive WBS reading increased by 4.773 (95% CI 3.701–5.845) for each percentage point increase in diagnostic test percent positivity (Appendix Figure 3).

**Discussion**

Percent positivity of COVID-19 diagnostic testing among jail residents correlated with SARS-CoV-2 detection in the jail wastewater during the same time periods, which provides evidence that WBS can serve as an indicator of viral infection within the jail. The study team’s inability to gather self-collected specimens from all jail residents in a single week supports the need for an aggregate indicator of population infection. Overall, our data indicate that WBS was a sensitive signal for COVID-19 cases in the jail population and of surges in infection (6,10,24,25).

The experience in this jail indicates that WBS can detect the beginning of an outbreak before

**Table 1.** Demographic characteristics of residents in the Fulton County Jail Main Complex, Atlanta, Georgia, USA, October 20, 2021–May 4, 2022\*

Characteristic	% Jail population
Reported sexual assignment	
M	98.4
F	1.6
Race/ethnicity	
Black, non-Hispanic	88.8
White, non-Hispanic	10.3
Hispanic	<1
Other	<1
Charges	
Misdemeanor only	6.8
Felony	93.2

\*Source: Fulton County Jail.

**Table 2.** Summary of COVID-19 diagnostic testing results at the Fulton County Jail, Atlanta, Georgia, USA, October 2021–May 2022\*

COVID-19 diagnostics weekly	Mean (SD) per week	Median per week	Minimum–maximum per week	Totals over entire study
No. diagnostic tests	491 (176)	443	267–961	13,745
No. rapid tests	356 (84)	363	186–554	9,975
No. PCR tests	222 (167)	186	20–591	3,770
% Jail population tested†	18.3 (7.1)	16	9.7–38.2	NA
Overall percentage positivity‡	3.39 (6.56)	0.55	0–29.5	NA

\*NA, not applicable.  
†Numerator is the number of positive test results in a given week, denominator is the jail population for the week.  
‡Numerator is the number of positive test results in a given week, denominator is the total tests for the same week

clinical signs appear. The spike in COVID-19 cases in the jail (January 5, 2022) occurred 8 days before a community surge in Fulton County and aligned with COVID-19 case surges in Atlanta and nationwide caused by the Omicron variant (24). Therefore, jails might serve as an early warning signal for community spikes for COVID-19 and other infectious diseases detectable in wastewater. This study also demonstrated the efficiency and feasibility of conducting WBS for SARS-CoV-2 on a regular basis in a jail setting. Although the median number of rapid ( $n = 363$ ) and PCR ( $n = 186$ ) tests differed during the study period, the strong correlation between the positivity rate of the 2 different tests ( $r = 0.65$ ;  $p < 0.01$ ) suggests relatively accurate results from both forms of diagnostic tests. Over the fall of 2021, the portion of the jail population that participated in the mass testing events (Figure 3) trended upward because of efficiencies introduced (Appendix).

As previous WBS studies on university campuses have noted, collecting and processing a few Moore swab samples in this study was faster and much less expensive than individual diagnostic testing of all jail residents (26). Because of this finding, there are still several functioning WBS programs, with potential to expand to other infectious diseases. A report on costs of WBS in this study is pending. Future work will examine the use of WBS to detect other pathogens present in the jail population, and possibly sequencing COVID-19 strains that are detected in the wastewater to contribute to molecular surveillance.

Strengths of this study include sufficient numbers of diagnostic tests and WBS samples to enable weekly comparisons between the 2 testing methods, and close collaboration with jail officials that provided the opportunity to conduct the study over a full 6-month period that captured temporal trends, including the entirety of the Omicron variant peak. Over the fall of 2021, the portion of the jail population that participated in the mass testing events for this study (Figure 3) trended upward because of efficiencies introduced (Appendix).

The first limitation of this study is that jail size precluded diagnostic testing of the entire jail population in any single week; percentage positivity from the portion tested for COVID-19 was used as a proxy. In addition, individual PCR tests were run outside of mass testing events as needed for the purposes of the jail's infection control program, not conducted simply for populationwide surveillance. Nonetheless, testing was never confined to jail areas known to have high or low COVID-19 prevalence. Second, the qRT-PCR results (Ct values) for the Moore swab samples are a semiquantitative indicator of SARS-CoV-2 concentration in wastewater because of the unknown volume of wastewater that passes through the swab (16). Third, a jail is not a closed system; many residents enter and leave daily. A resident who sheds fecal matter containing SARS-CoV-2 might leave the jail before the next round of individual COVID-19 screening and would therefore only be represented in the wastewater results. Fourth, only COVID-19 tests among residents were included in our analyses. However, because there are  $\approx 15$  times as many jail residents

**Table 3.** Spearman correlation coefficients ( $r$ ) for percentage positivity of diagnostic tests and wastewater Ct values within and between variable groupings, Fulton County Jail, Atlanta, Georgia, USA, October 20, 2021–May 4, 2022\*

Diagnostic test	$r$ (p value)		
	PCR	Rapid antigen	Total
PCR	Referent	0.91 (<0.01)	0.78 (<0.01)
Rapid antigen		Referent	0.97 (<0.01)
Total			Referent
Wastewater and diagnostic correlation¶			
Wastewater Ct values	-0.54 (0.048)	-0.64 (<0.01)	-0.67 (<0.01)

\*Percentage positivity for each category was computed by dividing the number of positive test results in 1 week by the total number of tests administered for the same week. Each datapoint is correlated with all other datapoints; none are grouped based on date or other variables. Ct, cycle threshold.

†Based on wastewater Ct values.

than staff, fecal material from staff probably had a negligible effect on the WBS results.

WBS was an efficient and accurate approach for tracking trends in SARS-CoV-2 infection in this jail population. Its most useful role might be as a sentinel surveillance tool when the signal switches from negative to positive, indicating a need for diagnostic testing in specific areas of the jail. Even under ideal circumstances with adequate resources, administering individual weekly COVID-19 diagnostic tests to the entire Fulton County Jail was not a feasible COVID-19 surveillance strategy. The WBS results aligned well with the percentage positivity of COVID-19 diagnostic tests among jail residents and could serve as a sensitive and economical surveillance tool for COVID-19 for this jail. In addition, because residents of the jail come from a wide geographic range in a large county, our results suggest that WBS at the jail could be useful for understanding COVID-19 trends in the jail itself to guide primary prevention and response to mitigate transmission and that jails could serve as a valuable sentinel site for monitoring trends in COVID-19 cases and genetic variants in the wider community.

### Acknowledgments

We thank Fulton County Sheriff Patrick Labat and the Sheriff's Office, Fulton County Jail staff, and the Fulton County Jail team members of NaphCare and Johnson Controls for assistance; residents of the Fulton County Jail who participated in this public health project; Jamie VanTassell and Lauren Briggman for wastewater sample collection; Orlando Sablon, Lizheng Guo, Matthew Cavallo, Caleb Cantrell, Jillian Dunbar for laboratory analyses; and Haisu Zhang, Lutfe-E-Noor Rahman, and Weiding Fang for wastewater data management and analyses.

This study was supported by the Bill and Melinda Gates Foundation (grant INV-035562) under the grant conditions of the foundation, a subcontract with Ceres Nanosciences for RADx Tech-Ceres Wastewater Testing, and National Institutes of Health prime award 75N92021C00012.

### About the Author

During this study, Ms. Saber was a project manager at Emory University, Atlanta. She is currently a Fulbright Research/Study grant recipient working in Kenya. Her primary research interests are understanding how use of water, sanitation, and hygiene interventions can prevent and survey for infectious disease on a global scale.


### References

1. Ayouni I, Maatoug J, Dhouib W, Zammit N, Fredj SB, Ghammam R, et al. Effective public health measures to mitigate the spread of COVID-19: a systematic review. *BMC Public Health*. 2021;21:1015. <https://doi.org/10.1186/s12889-021-11111-1>
2. Akiyama MJ, Spaulding AC, Rich JD. Flattening the curve for incarcerated populations: COVID-19 in jails and prisons. *N Engl J Med*. 2020;382:2075–7. <https://doi.org/10.1056/NEJMp2005687>
3. Minton TD, Zeng Z. Jail inmates in 2020 – statistical tables. Bureau of Justice Statistics. December 2021, NCJ 30330 [cited 2022 Aug 2]. <https://bjs.ojp.gov/content/pub/pdf/ji20st.pdf>
4. Centers for Disease Control and Prevention. Interim guidance on management of coronavirus disease. 2019 (COVID-19) in correctional and detention facilities, February 19, 2021, update [cited 2021 Apr 17]. [https://stacks.cdc.gov/view/cdc/100951/cdc\\_100951\\_DS1.pdf](https://stacks.cdc.gov/view/cdc/100951/cdc_100951_DS1.pdf)
5. Kirbiryk U, Binder AM, Ghinai I, Zawitz C, Levin R, Samala U, et al. Network characteristics and visualization of COVID-19 outbreak in a large detention facility in the United States – Cook County, Illinois, 2020. *MMWR Morb Mortal Wkly Rep*. 2020;69:1625–30. <https://doi.org/10.15585/mmwr.mm6944a3>
6. Hagan LM, McCormick DW, Lee C, Sleweon S, Nicolae L, Dixon T, et al. Outbreak of SARS-CoV-2 B.1.617.2 (Delta) variant infections among incarcerated persons in a federal prison – Texas, July–August 2021. *MMWR Morb Mortal Wkly Rep*. 2021;70:1349–54. <https://doi.org/10.15585/mmwr.mm7038e3>
7. Marusinec R, Brodie D, Buhain S, Chawla C, Corpuz J, Diaz J, et al. Epidemiology of coronavirus disease 2019 at a county jail, Alameda County, California, March 2020–March 2021. *J Public Health Manag Pract*. 2022;28:50–9. <https://doi.org/10.1097/PHH.0000000000001453>
8. Zawitz C, Welbel S, Ghinai I, Mennella C, Levin R, Samala U, et al. Outbreak of COVID-19 and interventions in a large jail, Cook County, IL, United States, 2020. *Am J Infect Control*. 2021;49:1129–35. <https://doi.org/10.1016/j.ajic.2021.03.020>
9. Hagan LM, Williams SP, Spaulding AC, Toblin RL, Figlenski J, Ocampo J, et al. Mass testing for SARS-CoV-2 in 16 prisons and jails – six jurisdictions, United States, April–May 2020. *MMWR Morb Mortal Wkly Rep*. 2020;69:1139–43. <https://doi.org/10.15585/mmwr.mm6933a3>
10. Tompkins LK, Gunn JKL, Cherney B, Ham JE, Horth R, Rossetti R, et al.; CDC COVID-19 Surge Diagnostic Testing Laboratory. Mass SARS-CoV-2 testing in a dormitory-style correctional facility in Arkansas. *Am J Public Health*. 2021;111:907–16. <https://doi.org/10.2105/AJPH.2020.306117>
11. Tsoungui Obama HJ, Adil Mahmoud Yousif N, Alawam Nemer L, Ngougoue PM, Ngwa GA, Teboh-Ewungkem M, et al. Preventing COVID-19 spread in closed facilities by regular testing of employees: an efficient intervention in long-term care facilities and prisons? *PLoS One*. 2021; 16:e0249588. <https://doi.org/10.1371/journal.pone.0249588>
12. Njuguna H, Wallace M, Simonson S, Tobolowsky FA, James AE, Bordelon K, et al. Serial laboratory testing for SARS-CoV-2 infection among incarcerated and detained persons in a correctional and detention facility – Louisiana, April–May 2020. *MMWR Morb Mortal Wkly Rep*. 2020;69:836–40. <https://doi.org/10.15585/mmwr.mm6926e2>
13. Gonzalez R, Curtis K, Bivins A, Bibby K, Weir MH, Yetka K, et al. COVID-19 surveillance in southeastern Virginia using wastewater-based epidemiology. *Water Res*. 2020;186:116296. <https://doi.org/10.1016/j.watres.2020.116296>

14. Betancourt WQ, Schmitz BW, Innes GK, Prasek SM, Pogreba Brown KM, Stark ER, et al. COVID-19 containment on a college campus via wastewater-based epidemiology, targeted clinical testing and an intervention. *Sci Total Environ.* 2021;779:146408. <https://doi.org/10.1016/j.scitotenv.2021.146408>
15. Gibas C, Lambirth K, Mittal N, Juel MAI, Barua VB, Roppolo Brazell L, et al. Implementing building-level SARS-CoV-2 wastewater surveillance on a university campus. *Sci Total Environ.* 2021;782:146749. <https://doi.org/10.1016/j.scitotenv.2021.146749>
16. Wang Y, Liu P, Zhang H, Ibaraki M, VanTassell J, Geith K, et al. Early warning of a COVID-19 surge on a university campus based on wastewater surveillance for SARS-CoV-2 at residence halls. *Sci Total Environ.* 2022;821:153291. <https://doi.org/10.1016/j.scitotenv.2022.153291>
17. Wu F, Xiao A, Zhang J, Moniz K, Endo N, Armas F, et al. SARS-CoV-2 RNA concentrations in wastewater foreshadow dynamics and clinical presentation of new COVID-19 cases. *Sci Total Environ.* 2022;805:150121. <https://doi.org/10.1016/j.scitotenv.2021.150121>
18. Karthikeyan S, Nguyen A, McDonald D, Zong Y, Ronquillo N, Ren J, et al. Rapid, large-scale wastewater surveillance and automated reporting system enable early detection of nearly 85% of COVID-19 cases on a university campus. *mSystems.* 2021;6:e0079321. <https://doi.org/10.1128/mSystems.00793-21>
19. Harris-Lovett S, Nelson KL, Beamer P, Bischel HN, Bivins A, Bruder A, et al. Wastewater surveillance for SARS-CoV-2 on college campuses: initial efforts, lessons learned, and research needs. *Int J Environ Res Public Health.* 2021;18:4455. <https://doi.org/10.3390/ijerph18094455>
20. Georgia Department of Community Affairs. Monthly jail reports [cited 2023 Aug 28]. <https://www.dca.ga.gov/node/830>
21. Sikorski MJ, Levine MM. Reviving the “Moore swab:” a classic environmental surveillance tool involving filtration of flowing surface water and sewage water to recover typhoidal *Salmonella* bacteria. *Appl Environ Microbiol.* 2020;86:e00060-20. <https://doi.org/10.1128/AEM.00060-20>
22. VanTassell J, Raymond J, Wolfe MK, Liu P, Moe C. Wastewater sample collection: Moore swab and grab sample methods. 2022 [cited 2023 Aug 23]. <https://www.protocols.io/view/wastewater-sample-collection-moore-swab-and-grab-s-81wgb6dnlpk/v1>
23. Sablon O, VanTassell J, Raymond J, Wolfe MK, Liu P, Moe C. Nanotrap KingFisher concentration/extraction and MagMAX KingFisher extraction. 2022 [cited 2023 Aug 13]. <https://www.protocols.io/view/nanotrap-kingfisher-concentration-extraction-amp-m-bp2l61ke5vqe/v1>
24. Svezia C, Nguyen A, VanTassell J, Raymond J, Wolfe MK, Liu P, et al. Singleplex qPCR for SARS-CoV-2 N1 and BRSV. 2022 [cited 2023 Aug 23]. <https://www.protocols.io/view/singleplex-qpcr-for-sars-cov-2-n1-and-brsv-bp2l61kqkvqe/v1>
25. Centers for Disease Control and Prevention. COVID data tracker. 2022 [cited 2023 Aug 23]. <https://covid.cdc.gov/covid-data-tracker>
26. Liu P, Ibaraki M, VanTassell J, Geith K, Cavallo M, Kann R, et al. A sensitive, simple, and low-cost method for COVID-19 wastewater surveillance at an institutional level. *Sci Total Environ.* 2022;807:151047. <https://doi.org/10.1016/j.scitotenv.2021.151047>

Address for correspondence: Anne C. Spaulding, Emory University, 1518 Clifton Rd, Atlanta, GA 30322, USA; email: [aspauld@emory.edu](mailto:aspauld@emory.edu)

## EID Podcast Isolation Cocoon, May 2020—After Zhuangzi’s Butterfly Dream



For many people, the prolonged period of social distancing during the coronavirus disease pandemic felt frightening, uncanny, or surreal.

For Ron Louie, the sensation was reminiscent of a moth taking refuge in its cocoon, slumbering in isolation as he waited for better days ahead.

In this EID podcast, Dr. Ron Louie, a clinical professor in Pediatrics Hematology-Oncology at the University of Washington in Seattle, reads and discusses his poem about the early days of the pandemic.

**Visit our website to listen:**  
<https://go.usa.gov/x6W9A>

**EMERGING  
INFECTIOUS DISEASES®**

*EID cannot ensure accessibility for Supplemental Materials supplied by authors. Readers who have difficulty accessing supplementary content should contact the authors for assistance.*

# Correlation of SARS-CoV-2 in Wastewater and Individual Testing Results in a Jail, Atlanta, Georgia, USA

## Appendix

### Comparison of Wastewater-Based Surveillance in Jails versus University Dormitories

Wastewater-based surveillance (WBS) has been studied in non-carceral institutions, such as university residence halls, where the turnover rate of those who reside in the dorm is low, and students normally live an entire semester in the same room but can have frequent visitors (1–6). In contrast, the median length of stay for a Fulton County Jail resident has historically been 5 days, and the mean stay is 22 days (7). This contrast between residence times in university dormitories versus a jail motivates a study specifically for the jail setting. There may be different utility of WBS data in jails compared with other settings.

### Dye Testing at Fulton County Jail to Trace Flow of Wastewater

For this study, we first assumed that the source of wastewater flowing under each manhole corresponded to only the zone of the building in closest proximity to the collection point. This assumption was tested by adding tracer dye (EcoClean Solutions, Copiague NY) into toilets in various housing blocks of the jail. When the dye from one housing block was detected in wastewater at multiple manholes, we concluded that the sewerage lines from multiple housing units were connected and that a wastewater sample from one manhole collection point could represent multiple housing blocks. Dye testing indicated that wastewater from both towers accumulated in Site 3 (See Figure 2, main manuscript), and the results from this site were used as a proxy for the wastewater concentration of SARS-CoV-2 for the entire jail.

### COVID-19 Individual Diagnostic Testing: PCR Nasal Swab Collection

Concurrent with initiating WBS, a team from Emory University began a mass diagnostic screening program in October 2021. We piloted self-collection of nasal specimens for PCR



testing by the jail residents by using a SteriPack swab [SteriPack, Lakeland FL], following a previously reported qualitative study of the acceptability of this novel specimen collection strategy (8). On dates when mass collection of nasal swabs was performed, we hired off-duty correctional officers to escort the Emory specimen collection teams to areas of the jail to distribute and retrieve the nasal swabs. Bar codes, pre-printed on the tubes, were scanned into a cloud-based registration portal system for the diagnostic testing laboratory (Northwell Health Laboratory, Lake Success, NY) and minimized the time from specimen collection to registration to less than a minute per swab. The direct scanning of barcodes into the portal also minimized human error by eliminating typing specimen codes into the portal. We shipped swabs overnight to the laboratory for RT-PCR analysis by an LGC, Biosearch Technologies SARS-CoV-2 ultra-high-throughput End-Point RT-PCR Test (BT-SCV2-UHTP-EP) to detect positive nasal swabs (Biosearch Technologies, Hoddesdon, UK).

During the fall of 2021, there was an upward trend in the portion of the jail population that participated in the mass testing events (Figure 3). This occurred by establishing an efficient screening method and improving our collection routine over time so that each swab could be gathered and registered in under a minute. The jail's housing configuration (cells rather than open dormitories) slowed the collection process. Nonetheless, we demonstrated that our process could achieve specimen collection from multiple housing units per hour.

## References

1. Wang Y, Liu P, Zhang H, Ibaraki M, VanTassell J, Geith K, et al. Early warning of a COVID-19 surge on a university campus based on wastewater surveillance for SARS-CoV-2 at residence halls. *Sci Total Environ.* 2022;821:153291. [PubMed https://doi.org/10.1016/j.scitotenv.2022.153291](https://doi.org/10.1016/j.scitotenv.2022.153291)
2. Karthikeyan S, Nguyen A, McDonald D, Zong Y, Ronquillo N, Ren J, et al. Rapid, large-scale wastewater surveillance and automated reporting system enable early detection of nearly 85% of COVID-19 cases on a university campus. *mSystems.* 2021;6:e0079321. [PubMed https://doi.org/10.1128/mSystems.00793-21](https://doi.org/10.1128/mSystems.00793-21)
3. Betancourt WQ, Schmitz BW, Innes GK, Prasek SM, Pogreba Brown KM, Stark ER, et al. COVID-19 containment on a college campus via wastewater-based epidemiology, targeted clinical testing and an intervention. *Sci Total Environ.* 2021;779:146408. [PubMed https://doi.org/10.1016/j.scitotenv.2021.146408](https://doi.org/10.1016/j.scitotenv.2021.146408)


4. Gibas C, Lambirth K, Mittal N, Juel MAI, Barua VB, Roppolo Brazell L, et al. Implementing building-level SARS-CoV-2 wastewater surveillance on a university campus. *Sci Total Environ.* 2021;782:146749. [PubMed https://doi.org/10.1016/j.scitotenv.2021.146749](https://doi.org/10.1016/j.scitotenv.2021.146749)
5. Liu P, Ibaraki M, VanTassell J, Geith K, Cavallo M, Kann R, et al. A sensitive, simple, and low-cost method for COVID-19 wastewater surveillance at an institutional level. *Sci Total Environ.* 2022;807:151047. [PubMed https://doi.org/10.1016/j.scitotenv.2021.151047](https://doi.org/10.1016/j.scitotenv.2021.151047)
6. Moody J. How Long Is a College Semester [cited 2023 Aug 23]. <https://www.usnews.com/education/best-colleges/articles/how-long-is-a-college-semester>
7. Spaulding AC, Kim MJ, Corpening KT, Carpenter T, Watlington P, Bowden CJ. Establishing an HIV screening program led by staff nurses in a county jail. *J Public Health Manag Pract.* 2015;21:538–45. [PubMed https://doi.org/10.1097/PHH.000000000000183](https://doi.org/10.1097/PHH.000000000000183)
8. González-Montalvo MD, Dickson PF, Saber LB, Boehm RA, Phillips VL, Akiyama MJ, et al. Opinions of former jail residents about self-collection of SARS-CoV-2 specimens, paired with wastewater surveillance: a qualitative study rapidly examining acceptability of COVID-19 mitigation measures. *PLoS One.* 2023;18:e0285364. [PubMed https://doi.org/10.1371/journal.pone.0285364](https://doi.org/10.1371/journal.pone.0285364)

**Appendix Table 1.** Descriptions of variables used for analysis of test results, Fulton County Jail, October 5, 2021 – May 4, 2022.


Variable	Description
PCR tests	Those tests in which SARS-CoV-2 virus was detected.
Jail population	The total resident population of the Fulton County Jail determined through the resident count on weeks that the study team received rosters from jail personnel (point count of the jail). On the weeks that no rosters were received, public records from the Georgia Department of Community Affairs (DCA) were used to estimate the jail population (Georgia Department of Community Affairs, 2022).
Positivity rate	The total number positive diagnostic tests (PCR plus rapid) in a week divided by the total number of tests administered in the same week.
Percent of jail tested	The total number of diagnostic tests (PCR plus rapid) administered in a week divided by the jail population in the same week.
Ct Value	RT-qPCR cycle threshold value measured in wastewater samples at the Emory laboratory by using primers and probes for the N1 gene of SARS-CoV-2

**Appendix Table 2.** Spearman correlation coefficients of all Ct value wastewater results between 4 manhole sites. All values were statistically significant ( $\alpha < 0.05$ ), October 2021–May 2022.

Site	Manhole 1	Manhole 2	Manhole 3	Manhole 5
Manhole 1	1			
Manhole 2	0.7437932	1		
Manhole 3	0.8324621	0.8945793	1	
Manhole 5	0.7075317	0.6935212	0.8041958	1




**Appendix Figure 1.** Percent positivity of both PCR and rapid diagnostic tests between October 2021–May 2022 at the Fulton County (Georgia) Jail.



**Appendix Figure 2.** Average Ct value of the four manholes for wastewater collection between October 2021–May 2022 at the Fulton County (Georgia) Jail. Final analysis used only site 3, due to high correlation between results from site 1, 2, and 4 with site 3.

$$\log \left( \frac{p}{1-p} \right) = \beta_0 + \beta_1 X,$$

**Appendix Figure 3.** Logistic regression of diagnostic test percent positivity and wastewater as a dichotomous outcome (positive or negative), Fulton County (Georgia) Jail, October 2021–May 2022. Where  $p$  is the probability of detecting SARS-CoV-2 in the wastewater sample from site 3 and  $X$  is the percent of positive COVID-19 diagnostic tests, the estimates of  $\beta_0$  and  $\beta_1$  were 0.484 and 4.773, respectively.



**Appendix Figure 4.** SARS-CoV-2 detected in wastewater at the Fulton County (Georgia) Jail, in diagnostic tests at the correctional facility, and in Fulton County from October 2021–May 2022. A) Dichotomous outcome of wastewater monitoring from four selected sampling point in the correctional facility, with blue tiles indicating a negative sample, red tiles indicating a positive sample, and any text representing average  $R_t$ -PCR Ct values. B) Percentage of positive wastewater samples from all sampling points in the correctional facility. Areas with a dot indicate that samples were collected that week. C) COVID-19 diagnostic test positivity rates. Areas with a dot indicate that samples were collected that week. D) Total reported cases in Fulton County, Georgia, with the line representing the 7-day average.