Reassessment of Internal Radiation Dose from Sources at the Rocky Flats Plant Critical Mass Laboratory

White Paper Rev. 0

National Institute for Occupational Safety and Health

November 28, 2016

James S. Bogard, Daniel Stempfley, Bob Burns Oak Ridge Associated Universities Team

Reviewed by LaVon Rutherford Division of Compensation Analysis and Support

Page 1 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

PURPOSE

This report reevaluates prior assumptions used to assess upper bounds on personnel doses from mixed fission and activation products (MFAP) at the Rocky Flats Plant (RFP) Critical Mass Laboratory (CML). A publicly released document citing a maximum reactor operating power of 10 milliwatts (mW) and a typical experiment duration of one hour were previously used to estimate the MFAP inventory built up over time in high-enriched uranium (HEU) solution fuel used in CML experiments. External radiation dose was monitored by radiation dosimeters assigned to each individual and has not been considered herein.

In the earlier assessment, internal doses from the estimated MFAP inventory were bounded by assuming removable surface contamination from dried solution spills to be at the limit for a posted Contamination Area. The average air concentration of respirable particles was then estimated by applying a resuspension factor. Recently captured documents contain air monitoring results, surface contamination measurements, more-accurate power estimates based on carefully measured gamma photon emissions from the irradiated fuel, records of experiment duration, and neutron flux profiles. This information provides data against which the prior assumptions can be re-evaluated.

MFAP PERSONNEL EXPOSURE CONCERNS

Fission products in irradiated fuels, and activation products in both the fuel and containment materials, are sources of external radiation dose to personnel using or working around the fuels, and they present an internal dose potential for personnel who might ingest or inhale them. Personnel dosimeters assigned to RFP radiation workers document the external exposures. Internal exposures might result: (1) during operations, from resuspension of contamination on surfaces, or (2) during facility demolition from airborne dust. CML staff was provided routine bioassay (urinalysis and whole-body counts) to detect intakes of plutonium, uranium, or americium, but MFAP were not routinely monitored.

Surface contamination in CML experimental areas was extensive, predominantly due to high-enriched uranyl nitrate (HEU) solution spills¹ over the course of the facility's history (Rothe, 2005, PDF pp. 447, 449, 452, 454-458, 464, 467-471, 479, 486, 498, 500-502). Thus, MFAP important from either an acute or chronic personnel internal exposure perspective are those generated by CML criticality experiments involving HEU solution. MFAP atom ratios on CML contaminated surfaces and resuspended in air from these surfaces are presumed to be the same as those in solution.


Page 2 of 51


¹ Eleven spills involved solutions or dried salts from solution experiments, compared with two contamination events involving other solid fuels (one spill each of low-enriched uranium and plutonium powders).

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

HISTORY OF UNH CRITICALITY EXPERIMENTS

Criticality experiments involving uranyl nitrate solution were conducted from the beginning of CML operations until the last experiment in 1987. These experiments are documented in some detail in a published history of the facility (Rothe, 2005, PDF pp. 376-394). Figure 1 shows the distribution of these experiments over time. Heights of the bars represent the average number of experiments per day during the Program period discussed in the published history; numbers above the bars are the total numbers of experiments. The dotted line shows the overall average number of HEU solution critical experiments over the history of CML operations.





Page 3 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

The 778 experiments performed at the CML with HEU solution or systems of HEU solution plus HEU metal took place in 10 campaigns between May 1967 and October 1987. Table 1 summarizes the 10 campaigns, where the "Downtime (d)" for each campaign equals the number of days between the last experiment of the specified campaign and the first experiment of the subsequent campaign.

Campaign	No. of Experiments	Downtime (d)
1	38	32
2	110	23
3	54	398
4	206	111
5	52	387
6	20	1,377
7	186	2,069
8	61	274
9	32	182
10	19	N/A

Table 1: CML Experimental Campaigns Involving HEU Solution

REEVALUATED FISSION AND ACTIVATION PRODUCT LEVEL ESTIMATES

NIOSH calculated fission and activation product build-up in uranium solution experiments at the CML using ORIGEN-S, a computer code system for calculating time-dependent concentrations of radionuclides that are simultaneously generated or depleted by processes such as fission, neutron absorption/transmutation, and radioactive decay. Initial assumptions about power levels and experiment durations were taken from a U.S. Department of Energy (DOE) public document that stated that the experiments conducted in Building 886 (housing the CML) generally involved power levels of no more than 10 mW for no more than one hour. It also stated that approximately half of the experiments conducted in Building 886 actually achieved criticality, and only rarely were the radiation levels such that it was not possible to directly touch the fissile material and testing apparatus immediately after the experiments (Building 886, 2011, PDF p. 3). Some of these assumptions were challenged during an oral interview with a former CML Associate Research Scientist, who asserted: (1) that the neutron flux for a CML experiment could not be bounded; and (2) that the best one could say is that the power level was probably less than 50 kW [the DOE Category B reactor limit] (Personal Communication, 2015a, PDF p. 9).

Documents subsequently captured by NIOSH contain neutron flux and thermal power estimates by CML staff using analytical measurements made during or after criticality experiments. These calculations were performed for at least three different enriched uranium fuel configurations: (1) bare HEU metal (Oy) spheres; (2) Oy spheres immersed in uranyl nitrate solution (UNH); and (3) UNH only.

Page 4 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

Thermal Power and Fission Rate Estimates in Bare Metal Experiments

Measurements of surface gamma photon fluence rates from a 7-cm-radius Oy sphere used in a 1967 one-hour criticality experiment led to an estimate of 1.9508×10^{-9} megawatts (MW) (1.9508 mW)² thermal power, corresponding with 2.18×10^{11} total fissions³ (Log, 1967, PDF p. 6).

Thermal Power and Fission Rate Estimates in Metal-Plus-Solution Experiments

CML staff made two estimates of total fissions in experiments involving Oy immersed in UNH. One 1976 estimate used the residual gamma photon flux from the Oy + UNH to estimate an upper bound of 1.8×10^{18} total fissions over the 12 years of CML operation from 1965-1976⁴ and an average power of 25 W (Log, 1976, PDF pp. 2-4). However, the senior scientist who performed the measurements and derived the estimate noted that the gamma photon background from a new unirradiated Oy part was the same as the gamma flux measured from irradiated parts used for the analysis. This means that measurements, made six years after the last criticality experiment, were unable to detect additional gammas from prior experiments because of radioactive decay of the fission and activation products. The original estimate did not take into account the intrinsic gamma photon emissions from unirradiated enriched uranium and was, therefore, invalid⁵ (Log, 1976, PDF p. 2).

A second estimate of 3.44×10^{10} fissions in an average Oy + UNH experiment with a 20-minute run time was derived by estimating the number of neutrons produced (8.4×10^{10}) using the current generated by a neutron detector associated with an April 1977 experiment (Experiments at RFNSF, 1977b, PDF p. 3). This fission rate corresponds with a thermal power level of 0.92 mW.

Thermal Power and Fission Rate Estimates in Solution-Only Experiments

The CML staff's most rigorous estimates of fission rates were derived for UNH (solution-only) fuel by measuring the rate of gamma decay in the fuel of Experiment 2-8-170. This experiment was configured as a 2×2 array of 8-in-diameter tanks and was performed on May 4, 1977 (Experiments at RFNSF, 1977a). The gamma photon count rate of a 2-mL aliquot withdrawn from the fuel after a 70.5-minute run was determined at 2- to 3-minute intervals using a "well crystal" calibrated to Cs-137 photons. The total number of fissions in the reactor was calculated

² The conversion from MW to mW in the reference document incorporated a factor of ten error, incorrectly concluding that the power level was 19.508 mW; the error is corrected here.

³ Using 1 W = 3.1×10^{10} fissions per second.

⁴ The estimate of total fissions is based on 27 days of continuous run time occurring in the middle of the 12-year period and corresponds with 7.7×10^{11} fissions per second.

⁵ The laboratory notebook entry reads: "All γ due to fission 6 years ago. (No believable background available.) Note: Part no. 80 never used and yet had same background/kg as others. [Therefore] Feel fission too low to detect by this method."

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

from the measured photon emission rate (Analysis Report, 1977, PDF p. 7) using Equation 1 below:

 $\dot{\Phi}_{\gamma} \cong 1.9 \times 10^{-6} \ \tau^{-1.2} \text{ photons/(second)(fission)}$

Where:

 $\dot{\Phi}_{\gamma}$ = Reactor gamma photon emission rate at time τ

 τ = Days after shutdown

An initial evaluation⁶ of the data (Introducing Nuclear Reactor Theory, 1977) arrived at a power estimate of 38 mW during the last 10 minutes of the experiment (when most of the corresponding 7.1×10^{11} fissions occurred), giving an average power of 5.4 mW for the 70.5-minute duration of the experiment.

⁶ Reactor power was evaluated using the integral of $\dot{\Phi}_{\gamma}$ over the operating time of the reactor, giving the gamma energy emission rate as a function of reactor power and time after shutdown.

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

A subsequent June 7, 1977 estimate from Experiment 2-8-170 employed more precise values for the aliquot and reactor volumes (Analysis Report, 1977, PDF p. 4). The estimate gave 25 mW at the end of the experiment, corresponding with 4.73×10^{11} fissions (or 3.6 mW, average power). These results were within 2% of those obtained by the method of source multiplication (Summary of All Nuclear Safety Experiments, 1977; Experiment Run 2-8-170, Undated), using Equation 2 below:

 $f = s \overline{\mu} t$

Where:

f = Total number of fissions over time t

t = Time

 $\bar{\mu}$ = Average multiplication from the neutron detector response during the experiment

s = Beginning neutron flux from the Cf-252 seed source

On June 3, 1977, before the more precise June 7 calculation was completed, CML staff communicated officially to the Energy Research and Development Administration (ERDA). They provided an estimate of 8.8×10^{11} fissions and an average power of 6.7 mW for a typical (70.5 minute) experiment (Tuck, 1977). There is no indication why the values reported to ERDA were almost 25% higher than results of the May 4, 1977 calculation.

Page 7 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

Conclusions about Reactor Power and Fission Rates in CML Experiments

Table 2 provides a summary of the different CML criticality experiments for which thermal power and fission rate were estimated from measurements.

Configuration	Duration	Average Power (mW)	Total Fissions	Fission Rate (s ⁻¹)	Comment
Оу	60 min	1.9508	2.18E+11	6.06E+07	Based on exposure rate at the surface of an Oy sphere converted to γ photon flux.
Oy + UNH (a)	27 d	25,000	7.7E+11	3.30E+05	Estimate is invalid; measurement results were indistinguishable from background.
Oy + UNH (b)	20 min	0.92	3.44E+10	2.83E+07	From neutron detector current.
UNH (a)	70.5 min	5.4	7.1×10 ¹¹	1.68E+08*	Initial calculation on May 4, 1977, for Experiment 2-8-170
UNH (b)	70.5 min	6.7	8.8E+11	2.08E+08*	Values reported to ERDA on June 3, 1977, based on results of Experiment 2-8-170.
UNH (c)	70.5 min	3.6	4.73E+11	1.12E+08	Recalculated values from Experiment 2-8-170 on June 7, 1977. Result is within 2% of that obtained from evaluation of source multiplication.

Table 2: Average Reactor Power and Fission Rates Derived from Measurements at CML

Source: Log, 1967, PDF p. 6 (Oy); Log, 1976 [Oy + UNH (a)]; Experiments at RFNSF, 1977b [Oy + UNH (b)]; Analysis Report, 1977, PDF p. 7 [UNH (a)]; Tuck, 1977 [UNH (b)]; Analysis Report, 1977, PDF p. 4 [UNH (c)]. *These values are not reported in the original reference, but are calculated from total fissions and duration.

CML staff described Experiment 2-8-170 to ERDA as having a higher-than-normal power level (Tuck, 1977, PDF p. 2). A thermal power estimate of 3.6 mW averaged over 70.5 minutes (corresponding with 4.73×10^{11} total fissions) is based on careful evaluation of measurements made on Experiment 2-8-170. NIOSH considers this the most precise estimate available for this relatively high-power experiment. CML staff, however, reported to ERDA an average thermal power of 6.7 mW over 70.5 minutes (8.8×10^{11} total fissions) based on the same experiment. NIOSH has concluded that the value reported to ERDA is the most appropriate value to represent the typical CML criticality experiments for the purpose of estimating doses from fission and activation products. This value is less than the earlier assumption that power averaged 10 mW for experiments lasting an hour (1.1×10^{12} total fissions). However, the value is still claimant-favorable because it exceeds the most careful estimate of power for the experiment, and because not all CML experiments achieved criticality (Building 886, 2011, PDF p. 3).

CML SURFACE CONTAMINATION

Radiological survey results

Internal doses from the estimated MFAP inventory were bounded in the earlier estimate by assuming that removable surface contamination from dried solution spills was evenly dispersed over CML surfaces at the DOE limit (1,000 dpm/100 cm²) for a posted Contamination Area. The average air concentration of respirable particles was then estimated by applying a

Page 8 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

resuspension factor. Recently captured documents contain both air monitoring and surface contamination measurement results against which the prior assumptions can be reevaluated.

Radiological survey results for Building 886 and 875 over the period January 1981 – December 1990 are captured in the following 105 files:

Radiological Surveys, 1980a-1980l; 1981a-1981m; 1982a-1982l; 1983a-1983k; 1984a-1984m; 1985a-1985m; 1986a-1986l; 1987a-1987e; 1988a-1988e; 1989a-1989g; 1990a, 1990b.

Information in these files includes results of daily removable contamination surveys in the office and experimental areas, and on equipment, as well as weekly penetrating-dose measurements in the nuclear material storage and experimental areas of Building 886.

Maximum Reported Values

Based on the data in the files listed in the subsection above, Table 3 shows the maximum reported values of removable alpha surface contamination for each year.

Year	Bldg. 886 Offices*	Bldg. 886 Experimental	Bldg. 886 Equipment	Bldg. 875 Outside	Bldg. 875 Inside
		Area**		Plenum	Plenum
1981	30	366	156	12	11196
1982	18	174 (3930)		12	14346
1983***	<20	576			
1984	<20	54000		<20	15660
1985	<20	174		<20	4788
1986	18	186 (2784)	3954	12	5394
1987	18 (24)	564			
1988	12	1683		12	15240
1989****	18	18707			
1990****	18	16212		6	

 Table 3: Maximum Removable Alpha Contamination (dpm/100 cm²)

Source: See the list of 105 files in the preceding subsection.

NOTE: Values in parentheses are singular outliers and not representative.

* "Offices" includes control points (corridors and common areas) typically surveyed daily and individual offices surveyed weekly.

**The experimental area (Rooms 101, 102 and 103) were surveyed weekly in 1981, but the frequency gradually diminished, apparently in response to decreased activities in these areas. Surveys were made approximately monthly by 1990.

***Data in 1983 are available only for November and December.

****Elevated values of this order were observed in weekly surveys of the Room 101 walk-in hood from December 1989 through April 1990, as discussed in the text.

Page 9 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

Based on the data in the files listed in the subsection above, Table 4 shows maximum gamma and neutron penetrating dose rates.

Year	Gamma* (mR/h): UNH Tank Room	Gamma* (mR/h): Solid Fuel Storage	Gamma* (mR/h): Experiment Room	Neutron** (mrem/h): UNH Tank Room	Neutron** (mrem/h): Solid Fuel Storage	Neutron** (mrem/h): Experiment Room
1981	2.0	2.9		0.3	12.9	
1982	2.0	2.5	3.7	0.2	14.7	5.4
1983						
1984	5.0	3.2		0.2	0.6	
1985	2.0	2.8		0.1	0.5	
1986	2.0	6.0	0.4	1.0	2.6	0.2
1987	3.0	2.0	3.0	1.7	2.0	3.4
1988	2.4	1.5	1.8	2.0	0.8	0.6
1989***	2.8	4.2 (250)	0.0	1.0	1.8 (6.0)	0.6
1990	2.53	3.0		0.3	0.5	

Table 4: Maximum Dose Rates in CML Experimental and Material Storage Areas

Source: See the list of 105 files in the preceding subsection.

NOTE: Values in parentheses are singular outliers and not representative.

*Gamma dose rate surveys were made at least weekly during the entire 10-year period.

** Neutron dose rate surveys were made weekly, along with gamma surveys, until 1990 when the frequency was reduced to monthly.

***Atypically-elevated dose-rate readings reported for July 6, 1989 are associated with a survey location within an area marked off inside the solid storage area.


Evaluation of Removable Contamination Survey Results

Contamination surveys were conducted daily at control points (hallways, doorways to offices), and weekly in offices within the unrestricted-access portion of Building 886. Surveys were conducted weekly in the experimental areas. Results of periodic contamination surveys in Building 875 and its air filtration plenums are also documented. Survey results for the office area are captured through December 20, 1990 (Radiological Surveys, 1990a, PDF p. 778), and for the experimental and material storage areas through April 1990 (Radiological Surveys, 1990a, PDF p. 330). No average values were found, except in 1989 documents, which contained a few graphs showing average contamination values in different areas for limited time periods (Radiological Surveys, 1989b, PDF pp. 3-6). These graphs are shown in Figures 2 through 5 below.

Page 10 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

Table 3 above, showing maximum values for the removable alpha survey results in both the office and experimental areas, demonstrates that radiological containment of the contaminated areas was quite effective. Excursions of removable contamination above the 20 dpm\100cm² DOE limit in "cold" (office) areas is seen to occur only a few times (and only at low levels) in 1981 and once in 1984. Survey results in offices and hallways were typically well below 20 dpm/100 cm², particularly toward the end of the period from 1981-1990 (e.g., see Figures 4 and 5).






Experimental and Material Storage Areas - Q1 1989

Page 11 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.




Source: Radiological Surveys, 1989b, PDF p. 5

Note: The solid line represents removable alpha contamination; the dashed line represents the DOE limit for uranium.

Figure 3: Average Removable Alpha Contamination in the Building 886 Experimental and Material Storage Areas – Q2 1989

Page 12 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.





```
Source: Radiological Surveys, 1989b, PDF p. 6
```


Figure 4: Weekly Averages of Removable Alpha Contamination in the Building 886 Offices and Control Points (Hallways and Conference Rooms) – Q1 1989

Page 13 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.







Review of the survey documents indicates that excursions of removable alpha contamination above the Contamination Area limit in the experimental area (Room 101) and the material storage area (Rooms 102, and 103) were usually reduced below 1,000 dpm/100 cm² within a few days, as noted below for entries in Table 3.

• The survey sheet showing $3,930 \text{ dpm}/100 \text{ cm}^2$ for removable contamination in Room 103 (the Mixing Room where uranium solution was housed) on September 10, 1982, for instance, has notation showing that the area was decontaminated to 12 dpm/100 cm² on the same day (Radiological Surveys, 1982c, PDF p. 23).

• A survey result of 54,000 dpm/100 cm² on February 27, 1984 (the highest found in any of the captured documents), was located in the walk-in hood of Room 101 (Radiological Surveys, 1984c, PDF p. 13). A second survey sheet with the same date shows <20 dpm/100 cm² for all

Page 14 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

survey locations in Rooms 101, 102 and 103, and bears he hand-written note, "Retake of survey after [name redacted] and [name redacted] cleaned all of Rm 101."


• The high value of 2,784 dpm/100 cm² in 1986 is reported on a survey sheet dated June 17, along with the handwritten notation, "Table Top 3954 d/m/100 cm²; Rest of Table 25.8 d/m/100 cm²; deconned 6/18/86" (Radiological Surveys, 1986c, PDF p. 8). The survey sheet for June 18, 1986 indicates that all results in the controlled area were \leq 24 dpm/100 cm² (Radiological Surveys, 1986c, PDF p. 9).

• The 1988 high result of 1,683 dpm/100 cm² was found just outside the walk-in hood of Room 101 on October 7, 1988 (Radiological Surveys, 1988d, PDF p. 37). A similar elevated result (1,422 dpm/100 cm²) was found inside the hood. Contamination at the location outside the hood was reduced to 60 dpm/100 cm² a week later, on October 14 (Radiological Surveys, 1988d, PDF p. 38), but the elevated value inside the walk-in hood persisted. It was reduced to 126 dpm/100 cm² in the October 21 survey report (Radiological Surveys, 1988d, PDF p. 39).

Prompt decontamination practices were evident during most of the period from 1981-1990; however, elevated contamination levels in the Room 101 walk-in hood were recorded in December 1989 and persisted through April 1990. The persistent contamination is reflected in the maximum-recorded values of 1989 and 1990 shown in Table 3 above, and is detailed in the weekly contamination survey results presented in Table 5 below. The FBI raid of Rocky Flats in June 1989 resulted in the curtailment of plutonium operations. Subsequently, the plant's resources were redirected toward remediation of the issues resulting from the raid. According to the document, *A Technically Useful History of the Critical Mass Laboratory at Rocky Flats*, "Manpower was not available to decontaminate Room 101 in the late 1980s because Maintenance personnel had all been dedicated to solving the plant's larger problems" (Rothe, 2005, PDF p. 395). Handwritten notes on the survey sheets sometime indicate that full-face respirator protection was required in Room 101 when contamination levels exceeded the DOE limit (e.g., Radiological Surveys, 1989b, PDF p. 109). Figure 6 shows the floor plan for Room 101, where criticality experiments were performed; the walk-in hood is the enclosure left of center.

Page 15 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.



Source: Rothe, 2005, PDF p. 120

Figure 6: Floor Plan of the Assembly Room (Room 101), Showing the Walk-in Hood Containing the Vertical Split Table (V) and Solution Base (S) Experimental Locations

Page 16 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

Tuble	Location 20* Location 21* Location 22*						
Date	$(dpm/100 \text{ cm}^2)$	$(dpm/100 cm^2)$	$(dpm/100 cm^2)$	Reference	PDF p.		
Dutt	(upin/100 cm)	(upin/100 cm)		Radiological	121 p		
11/21/1989	27	642		Surveys, 1989b	92		
11, 21, 19 09	_,	0.2		Radiological	/-		
11/30/1989	239			Surveys, 1989b	116		
				Radiological			
12/7/1989	897	12579	18707	Surveys, 1989b	160		
				Radiological			
12/14/1989	9	100	90	Surveys, 1989b	183		
				Radiological			
12/21/1989	72	51	5235	Surveys, 1989b	196		
				Radiological			
1/18/1990	168	693	6990	Surveys, 1990a	60		
				Radiological			
1/25/1990	84	672	6963	Surveys, 1990a	81		
				Radiological			
2/1/1990	93	1230	12219	Surveys, 1990a	99		
				Radiological			
2/8/1990	105	1290	13452	Surveys, 1990a	117		
- // - //		1	40000	Radiological			
2/15/1990	255	15099	10839	Surveys, 1990a	135		
2/22/1000	717	102.00	0070	Radiological	150		
2/22/1990	717	12369	9978	Surveys, 1990a	156		
2/1/1000	(20)	14162	(022	Radiological	171		
3/1/1990	639	14163	6933	Surveys, 1990a Radiological	171		
3/8/1990	616	14193	6987	Surveys, 1990a	183		
5/8/1990	010	14195	0987	Radiological	185		
3/15/1990	468	12423	7923	Surveys, 1990a	207		
5/15/1770	400	12425	1725	Radiological	207		
3/22/1990	1035	16212	5403	Surveys, 1990a	234		
5/22/1990	1055	10212	5105	Radiological	231		
3/29/1990	1893	15708	7842	Surveys, 1990a	252		
				Radiological			
4/5/1990	2748	12951	8967	Surveys, 1990a	273		
				Radiological			
4/19/1990	2556	14967	13683	Surveys, 1990a	291		
				Radiological			
4/12/1990	1572	13593	10353	Surveys, 1990a	300		
				Radiological			
4/26/1990	2037	14463	11973	Surveys, 1990a	330		

 Table 5: Room 101 Walk-In Hood Contamination Results, November 1989 – April 1990

*Locations 20, 21, and 22 correspond with the entry portal, Solution Base (S), and Vertical Split Table (V), respectively, as shown on the floor plan in Figure 6 above.

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

Air flow through Room 101 came from outside through the walk-in hood to the exhaust plenum in Building 875, and through HEPA filters before being exhausted to the outside air. The walk-in hood was, therefore, at a lower pressure than Room 101, drawing resuspended contamination to the exhaust plenum and not into the rest of Room 101. This engineered feature reduced exposure to Room 101 personnel and, along with workforce priorities redirected as a result of the FBI raid, probably explains why the hood was not decontaminated in late 1989 and 1990. The last CML criticality experiment concluded in October 1987 (Rothe, 2005, PDF p. 393); no routine work was performed in Room 101 after this date, further reducing the potential for personnel exposure as the result of contamination in the walk-in hood in 1989 and 1990.

Additional CML Personnel Identified for 1989

The 1989 files were different from those in other years because the forms (Radiological Surveys, 1989b) were signed by the RCTs who were making the measurements. Based on the additional research performed for this review, NIOSH has identified no NOCTS claims associated with the seven individuals signing the survey forms.

Discovery of Sealed Sr-90 Sources

The file of survey results for June 1982 contains a copy of a note detailing radiological characteristics of three sealed Sr-90 sources (Radiological Surveys, 1982k, PDF p. 3). The note is reproduced as Figure 7 below. It is the only documentation in hand indicating the presence of Sr-90 at CML. There is no information about why the sources were at CML, how long they might have been there, or their disposition. Integrity of the source encapsulations was confirmed by removable contamination surveys of the sources and the cabinet in which they were found.

Page 18 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

6/2/82 3- Sr. 90 Sulfate Sealed 6/56 Fack container reads @ surface - Victoreen - 25 Mgh All three containers @ 3 ft. - Unterren - 20.5 Each container reads @ surface - Ludlam 31 - 200 K All three containers @ 3ft - Ludlum 31 - 1K Outside reading when placed in cabinet W/Ludlum 71 750 c/m W/Victorern <0.5 No smear count from either container Cabinet had no smear count

Source: Radiological Surveys, 1982k, PDF p. 3

Figure 7: Memo on β-γ Penetrating and Removable Surface Contamination Measurements Made upon Discovering Three Sealed Sr-90 Sources in the Building 886 Material Storage Area

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

Conclusions About Surface Contamination at CML

Surveys for removable alpha contamination at CML were conducted regularly. Excursions above the applicable DOE limits (20 dpm/100 cm² in uncontrolled office areas and 1,000 dpm/100 cm² in controlled-access experimental areas) were confined to discrete areas and were quickly decontaminated below the limits. Values above the limit in uncontrolled areas were only rarely observed. The largest measured value for removable contamination was 54,000 dpm/100 cm², found at sampling location 21 in the walk-in hood (Radiological Surveys, 1984c, PDF pp. 13, 14). This amount of contamination, if spread uniformly over the entire surface area⁷ of the controlled area, would be 1,800 dpm/100 cm²; it was decontaminated on the same day it was found. All other values for removable contamination captured by NIOSH correspond to <1,000 dpm/100 cm², if distributed uniformly. All were quickly decontaminated, except for that in the walk-in hood from November 1989 – April 1990, which was contained and ventilated during a time of little or no personnel activity in Room 101.

In light of the above information, the assumption that average removable contamination available for resuspension in the experimental and material storage areas (Rooms 101, 102, and 103) was equal to or less than the Contamination Area limit of 1,000 dpm/100 cm² is claimant-favorable.

CML WORKPLACE AIR MONITORING

Bounds on internal dose from MFAP were previously based on airborne concentrations calculated by applying a resuspension factor to surface contamination limits posted for the facility. This approach was based on interview comments from a former Radiation Safety Supervisor, who said that no routine air monitoring was performed at the CML prior to 1990, when this individual was assigned responsibility for Building 886 (Personal Communication, 2015b, PDF pp. 4, 7). NIOSH has since captured formal plant-wide procedures describing a particulate air monitoring program during the period from 1980-1989 for alpha-particle emissions from uranium, plutonium, and americium at sampling locations selected by process knowledge or professional judgment. Additional captured documents indicate that these procedures appear to have been followed and that routine alpha air monitoring was performed at the CML during the period 1980-1989.

⁷ Dimensions of the walk-in hood (Rothe, 2005, PDF p. 129) in Room 101 were 3.0 m \times 4.9 m. Sampling location 21 was located in a part of the hood comprising about half this surface area, or 7.35 m². Estimated floor areas for the individual rooms are 120 m² for Room 101 (Rothe, 2005, PDF p. 120); 40 m² for Room 103 (Rothe, 2005, PDF p. 167); and 60 m² for Rooms 102 and 108 (connecting hallway) combined, assuming this area to be about half that of Room 101 (Rothe, 2005, PDF p. 110). The total estimated floor area is the sum of these values, or 220 m². Distributing the contamination at sampling location 21 over the entire surface area would result in an average contamination level reduced by the ratio 7.35/220.

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

Rocky Flats Plant Workplace Air Monitoring Requirements

Formal procedures describe monitoring requirements and practices for routinely evaluating concentrations of alpha-emitting particulates (U, Pu, and Am) in Rocky Flats workplace air over the period from 1979 through 1990 (Radiation Monitoring Technical Support Programs, 1976, PDF pp. 19-136). The earliest captured procedure (issued November 1979) and its subsequent revisions through December 1990 are listed below:

• *Routine Air Sampling*, HS-RM-4.1, November 13, 1979 (Radiation Monitoring Technical Support Programs, 1976, PDF pp. 19-29)

• *Routine Air Sampling*, RMPM 4.1, August 2, 1982 (Radiation Monitoring Technical Support Programs, 1976, PDF pp. 30-43)

• *Routine Air Sampling*, RMPM 4.1, January 13, 1989, Replaces: August 2, 1982 (Radiation Monitoring Technical Support Programs, 1976, PDF pp. 65-81)

• *Routine Air Sampling*, RMPM 4.1, June 1989, Replaces: January 13, 1982 (Radiation Monitoring Technical Support Programs, 1976, PDF pp. 44-64)

• *Routine Air Sampling*, ROI 4.1, December 18, 1989, Replaces: June 15, 1989 (Radiation Monitoring Technical Support Programs, 1976, PDF pp. 102-118)

• *Routine Air Sampling*, ROI 4.1, Rev. 3, December 20, 1990, Replaces: December 19, 1989 (Radiation Monitoring Technical Support Programs, 1976, PDF pp. 119-136)

Page 21 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

Review of the procedures shows consistent requirements for calibrating monthly both Gross Alpha (Continuous) Air Monitors (CAMs) and Selective Alpha Air Monitors (SAAMs). CAM filters were collected and sent for analysis each weekday (Monday – Friday), except holidays, until at least January 1989, when RMPM 4.1 specified that the exchange frequency was to be determined by Operational Health Physics personnel (Radiation Monitoring Technical Support Programs, 1976, PDF p. 67). Subsequent revisions assigned the responsibility for establishing sampling frequencies to Building 123 Count Room personnel (Radiation Monitoring Technical Support Programs, 1976, PDF p. 49), Operational Health Physics (Radiation Monitoring Technical Support Programs, 1976, PDF p. 104), or to Radiological Engineering personnel (Radiation Monitoring Technical Support Programs, 1976, PDF p. 121). When collected, filters were monitored with a hand-held alpha survey instrument. Filters with excessive alpha activity were held for specified periods before analysis to allow decay of the short-lived radon and thoron progeny; a time-dependent Koval factor was applied to the analytical results to account for undecayed progeny (Radiation Monitoring Technical Support Programs, 1976, PDF pp. 22-23, 36-37, 52, 72). Final results were reported as percentages of the radioactive concentration guide (RCG) airborne limit for the material in question, or 70 dpm/m³ for uranium⁸ (Radiation Monitoring Technical Support Programs, 1976, PDF pp. 25, 39, 73). In June 1989, the airborne limit for uranium (in any form) was changed to 44 dpm/m³, corresponding to the DOE Order 5480.11 Derived Air Concentration (Radiation Monitoring Technical Support Programs, 1976, PDF pp. 54, 104, 121).

Air Sampling Locations

Air particulate samplers were located in Buildings 886 and 875, as marked on monthly air head calibration sheet maps (Calibrations, 1987; Calibrations, 1988; Calibrations, 1989a; Calibrations, 1989b); Figure 8 shows an example. The locations appear to be unchanged during the period from 1980-1989. Building 875 housed the air exhaust plenums from the Building 886 experimental (Room 101) and material storage (Rooms 102 and 103) areas. The air head samplers were numbered RR-1 through RR-11 and fixed in the locations listed below:

Building 886

- RR-1 through RR-4, Room 103 (material storage)
- RR-5, Room 102 (material storage)
- RR-6 and RR-7, Room 101 (experimental area)

⁸ The RCG used by Rocky Flats in its air-sampling program corresponds with the Maximum Allowable (air) Concentration (MAC) used by AEC contractors in referring to the AEC's "preferred level" of 50 μ g/m³ for all uranium compounds on the basis of chemical toxicity. The level was also stated as 70 dpm/m³ for natural uranium. (ORAUT-OTIB-0004, 2006, PDF p. 8)

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

Building 875

- RR-8 and RR-9, outside the plenum
- RR-10, inside the first plenum
- RR-11, inside the tunnel from Building 886


SAAM samplers also were located in Rooms 101-103 of Building 886 and in the second plenum of Building 775. The detectors on these samplers were equipped with high-voltage discriminators that registered only alpha energies above a certain threshold, providing a means to discriminate against lower-energy alpha emitters that would otherwise give false alarms. The filter media from SAAMs were normally discarded without analysis unless the instrument had alarmed or the filter failed a hand-held radiation monitor check (Radiation Monitoring Technical Support Programs, 1976, PDF pp. 26, 35, 51, 70, 88, 105-106, 123).

Other air sampling results from 1981-1988 for samples labeled "875-A", "875-B" and "875-C" have also been captured but their locations in Building 875 have not been identified (Air Samples, 1981a, 1981b; 1982a-1982i; 1983a, 1983b; 1984a-1984d; 1985a-1985e; 1986a-1986m; 1987a; 1988a-1988g).


CML personnel did not routinely access Building 875, and consideration of air monitoring results for this building is limited to those in the "RR" series, with known locations and direct correlation with daily samples from Building 886.

Page 23 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.



Source: Calibrations, 1987, PDF p. 6



Air Sampling Results

NIOSH has captured air sample results in 41 of 120 months during the period 1980-1989. Results from samplers RR-1 through RR-7 (Building 886) and RR-8 through RR-11 (Building 875) are available for the period December 1980 to June 1989, although all but two of the results fall in the period from May 1983 to November 1988. The data, summarized in Table 6, indicate that procedural requirements for daily air monitoring appear to have been met at the CML. The number of analytical results per month for a particular sampler location is expected to be between 19 and 22, depending on the number of work days. In the captured data, daily sample collection is demonstrated with certainty (results available for 19 or more days) in 15 of the 41 months (37% of the time for which records are available, but only 1% of the period from

Page 24 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

1980-1989). Sample collection on at least alternate days, on average (results available for 10-18 days), is demonstrated with certainty during an additional 10 months. The availability of air sampling data does not seem to correlate with known spills or criticality experiments. Only one sampling day's results were captured during operations prior to 1983, but 207 sampling days correspond with three operational periods after 1983. Four contamination incidents occurred from 1980-1989, but air monitoring results were only captured for the time period in which two incidents occurred closely together in 1987. Experiment periods, contamination incident dates, and associated records of airborne contamination results are summarized in Table 7.

Page 25 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

Storage and Experimental Areas No. of Days No. of Days ≥100%					
Year	Month	References	Sample Days*	10%-99% RCG**	RCG**
1980	Dec	Air Samples, 1980	1		
1983	May	Air Samples, 1983c	2		
1983	Sep	Air Samples, 1983d	1		
1983	Oct	Air Samples, 1983e	17	2	
1984	Jul	Air Samples, 1984e	2		
1984	Aug	Air Samples, 1984f	22	1	1
1984	Sep	Air Samples, 1984g	19	2	
1984	Oct	Air Samples, 1984h	20	6	
1984	Nov	Air Samples, 1984i	22	8	3***
1984	Dec	Air Samples, 1984j	15	5	
1985	Jan	Air Samples, 1985f	19	4	
1985	Feb	Air Samples, 1985g	19	8	2
1985	Mar	Air Samples, 1985h	22	1	
1985	Apr	Air Samples, 1985i	21		
1985	May	Air Samples, 1985j	22	3	
1985	Jun	Air Samples, 1985k	22		
1985	Jul	Air Samples, 19851	23	2	
1985	Aug	Air Samples, 1985m	20	2	
1985	Sep	Air Samples, 1985n	15		
1985	Oct	Air Samples, 19850	9		
1985	Nov	Air Samples, 1985p	19	1	
1985	Dec	Air Samples, 1985q	15		
1986	Jan	Air Samples, 1986n	19		

 Table 6: Air Sample Results Summary for the CML Building 886 Nuclear Materials

 Storage and Experimental Areas

Page 26 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

Year	Month	References	Sample Days*	No. of Days 10%-99% RCG**	No. of Days ≥100% RCG**
1986	Feb	Air Samples, 19860	1		
1986	Jun	Air Samples, 1986p	4		
1986	Jul	Air Samples, 1986q	14		
1986	Nov	Air Samples, 1986r	3		
1986	Dec	Air Samples, 1986s	9		
1987	Jan	Air Samples, 1987b	15	1	
1987	Feb	Air Samples, 1987c	22		
1987	Mar	Air Samples, 1987d	8		
1987	May	Air Samples, 1987e	6		
1987	Jul	Air Samples, 1987f	3		
1987	Aug	Air Samples, 1987g	13		
1987	Sep	Air Samples, 1987h	7		
1987	Dec	Air Samples, 1987i	11		
1988	Jan	Air Samples, 1988h	18		
1988	Feb	Air Samples, 1988i	15		
1988	Apr	Air Samples, 1988j	5		
1988	Nov	Air Samples, 1988k; 1988l	5		
1989	Jun	Air Samples, 1989	1		
TOTAL	N/A	N/A	526	46	6

NOTE: Documents captured by NIOSH include results from only portions of years 1980 and 1983-1989, as shown in the table.

* The number of days in the specified month for which captured air-monitoring data indicate that samples were collected. Procedures required that sample filters be changed and analyzed daily, except over weekends and holidays.

** The number of days for which the specified fraction of the uranium Radiological Control Guide (RCG) of 70 dpm/m³ alpha was met or exceeded.

*** Notations on the air results indicate that respirators were worn.

Page 27 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

Containination Results						
Experimental Campaigns*	Contamination Incident Dates**	Airborne Monitoring Days Captured				
None	11/25/1980	0				
02/1978 - 09/1981	None	1				
Summer 1982 – 12/20/1982	None	0				
05/1983 - 09/1984	None	64				
None	07/07/1984 - 07/20/1984	0				
07/1985 - 08/1986	None	139				
None	02/14/ 1987 & 03/13/1987	30				
04/1986 - 10/1987	None	104				

 Table 7: Experiment Periods, Contamination Incident Dates, and Associated Records of Airborne Contamination Results

*Rothe, 2005, PDF pp. 389-393

**Rothe, 2005, PDF pp. 486-487, 498, 500-501

Building 886/875 results appear in the same reports as those for Building 865, which housed the Metal Research and Development Laboratory⁹ and which processed non-plutonium metals, including depleted uranium (DOE, 2011, PDF p. 2). Reports are reviewed and initialed, and instructions on the report sheet specify that a copy is to be sent "TO RADIATION MONT 881" (to Radiation Monitoring, Building 881).

Individual sample results are occasionally lined out in the reports, with or without explanation. There are multiple instances when results are lined out with the notation "W/C" or "Wrong Color." The meaning of this notation is not clear, and these samples are not included in evaluating the results.

A total of 526 days of results were evaluated against the Radiological Control Guide (RCG) of 70 dpm/m³. One or more results from the seven samplers in Building 886 exceeded the RCG on six days; results between 10% and 100% of the RCG were recorded on 46 additional days. All results were below 10% of the RCG for the remaining 473 days. Respirators were worn on three of the six days in which the RCG was exceeded (Air Samples, 1984e, PDF pp. 33, 36, 52). Results on the other three days in which the RCG was exceeded were: 522.02% RCG (Air Samples, 1984f, PDF p. 5); 111.72% RCG (Air Samples, 1985f, PDF p. 37); and 117.76% RCG (Air Samples, 1985f, PDF p. 41).

Results from Building 875, which housed the effluent air exhaust plenums from the Building 886 experiment room, exceeded the RCG on only one occasion¹⁰ during the same 526 days; results between 10% and 100% of the RCG were recorded on two days.

Page 28 of 51

⁹ Each day's results for Building 886 are labeled RR-1 through RR-7; those for Building 875 are labeled RR-8 through RR-11; Building 865 results begin with a "UU-" designator.

¹⁰ The sample designation was "RR-12" for the single result exceeding the RCG, without explanation of the location or purpose for the sample. A location in Building 875 is assumed.

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

Conclusions About Workplace Air Monitoring at the CML

NIOSH concludes that a robust and well-defined workplace air-monitoring program for alpha-emitting radioisotopes was required by Rocky Flats plant procedures on continuing basis during the period 1980-1989. In all air-monitoring records captured by NIOSH, air particulate samples from the CML, Building 886, and its air exhaust filtration plenums in Building 875, were routinely analyzed and reported along with those from the Metal Research and Development Laboratory, Building 865. Sampling results were evaluated for uranium alpha emissions and reported as a percentage of the radioactive concentration guide (RCG) airborne limit for uranium, 70 dpm/m³. The analytical reports were reviewed and initialed, and were to be sent to Radiation Monitoring in Building 881. Excursions in excess of the RCG were uncommon, occurring in Building 886 on six of 526 days for which monitoring results were captured, and in Building 875 only once.

A bounding value for activity concentrations in breathing air can be calculated as the weighted average \bar{C} of air results using recorded values for three results in excess of the RCG with no indication that respirators were worn, and by making the claimant-favorable assumptions that results were 70 dpm/m³ for 46 results between 10% and 100% of RCG and 7 dpm/m³ for the remaining 477 recorded samples, as shown in Equation 3 below:

$$\bar{C} = \frac{[5.22 + 1.12 + 1.18 + (46)(1.0) + (477)(0.1)] \text{ RCG days}}{526 \text{ days}} = 0.1924 \text{ RCG}$$
$$= 13.5 \text{ dpm/m}^3.$$

Results for the 526 days of monitoring data captured for the period 1980-1989 are assumed to be representative of uncaptured data for that period for the following reasons:

- The same plant health physics procedures requiring air monitoring were in effect continuously (with revisions) for the entire period;
- NIOSH assumes that daily samples were collected and analyzed in accordance with plant procedures over the entire period; and
- The results are probably similar because CML operations were similar over the period.

These data were available for routine review by health physics personnel, who also had access to information about operations for making personnel monitoring decisions. It is therefore unlikely that an unrecorded intake of alpha contaminated airborne particulates occurred during this period because of a lack of relevant air monitoring data.

Page 29 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

ASSESSMENT OF UNMONITORED RADIATION DOSE AT THE CML

Radiation dose from intake of MFAP at CML could have occurred during clean up of numerous fuel spills, predominantly from enriched uranyl nitrate solution (UNH), or from inhalation of dried, resuspended contamination deposited on surfaces as the result of these spills (Rothe, 2005, PDF pp. 447-449, 452-462, 464-473, 486-487, 498, 500-501). Rocky Flats workers (including those assigned to the CML) with the potential for receiving intakes of plutonium, americium, or uranium were monitored by periodic urinalysis and body counts (NIOSH, 2006, PDF p. 30). However, NIOSH has found no indication that confirmatory bioassays were performed for employees involved in clean up of any of the accidental UNH spills. Fission and activation products, which decay primarily by beta/gamma emission, are not likely in any case to have been detected by bioassay intended to detect alpha particles emitted by uranium or transuranic radionuclides.

Maximum MFAP internal doses to CML workers were estimated by modeling a representative UNH experiment and calculating the MFAP inventory based on the historical record of CML experiments with UNH, and on the average thermal power and duration of CML UNH criticality experiments reported by CML researchers. Intakes of resuspended UNH contamination with the same MFAP-to-uranium atom ratio as the fuel were estimated from the weighted average of air monitoring results in the experimental and materials storage areas of the CML. Doses were calculated by applying ICRP 68 (ICRP, 1995) dose conversion factors for three solubility categories of dosimetrically significant radionuclides, using the method described in ORAUT-OTIB-0054 (2015).

Calculation of Fission and Activation Product Content of UNH Solution

A series of experiments was performed at the CML during the mid-1970s to determine the critical height of UNH in suspended, cylindrical tanks. Experiments were performed using different uranium concentrations, different tanks, and with and without neutron reflectors. The same uranium enrichment was used in all experiments; only the concentration was varied.

NIOSH chose one of the unreflected suspended tank experiments from the mid-1970s to represent UNH experiments performed over the CML's history. There were ten unreflected suspended tank experiments in all. Two of them used a stainless-steel tank and the remainder used an aluminum tank.

NIOSH selected one of the experiments that used the stainless-steel tank so that the calculated fission and activation product content would include iron activation products. The tank had an inside diameter of 27.92 cm and an inside height of 41.6 cm. For the selected experiment, the tank was filled with UNH with a uranium enrichment of 93.172 weight percent U-235 at a concentration of 145.68 g/L. The other unreflected stainless steel tank experiment used UNH with the same enrichment, but at a concentration of 346.73 g/L. The lower concentration was selected because it represents the middle of the range of concentrations used across the ten unreflected tank experiments. The critical solution height for the selected experiment was found

Page 30 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

to be 31.20 cm. The selected experiment is documented as Case Number 1 in "Minimally Reflected Cylinders of Highly Enriched Solutions of Uranyl Nitrate," HEU-SOL-THERM-001, from the *International Handbook of Evaluated Criticality Safety Benchmark Experiments* (Palmer, 2004).

The fission and activation product composition for the selected experiment was calculated using SCALE. SCALE is a modular system of computer codes for nuclear- and radiological engineering-related analyses from the Oak Ridge National Laboratory. SCALE's TRITON module was used to develop a case-specific cross-section library for the selected suspended tank experiment. The case-specific library was then used by the ORIGEN-S code to determine the time-dependent fission and activation product content of the UNH and the stainless-steel tank over the CML's history.

The TRITON module performs neutron transport and depletion calculations for irradiated nuclear fuels. Neutron transport is performed using either discrete ordinates methods (via the NEWT code) or via Monte Carlo calculations (using the KENO –V or KENO-VI codes). TRITON's capabilities include creating case-specific cross-section library files that can be used by other elements of the SCALE code system, notably the ORIGEN-S code. Among the numerous capabilities of ORIGEN-S is calculation of the inventory of activation products, actinides, and fission products in a composition as a function of time and burnup (as applicable).

TRITON was used to model the stainless-steel tank and UNH solution geometry of the selected suspended tank experiment as a system of cylinders representing the tank bottom, tank walls, and the UNH volume. The tank and solution heights were truncated to the critical solution height of 31.20 cm. Neutron transport was performed via the KENO-VI Monte Carlo code.

The case-specific cross-section library created by TRITON was subsequently used in an ORIGEN-S calculation to determine the fission and activation product content of the solution, and the tank volume at the end of the tenth campaign and thereafter. This reflects a modeling assumption that the same tank and solution were used for all 778 experiments involving HEU solutions performed at the CML over its operating history. The composition used for the ORIGEN-S calculations was a homogenized mixture of the HEU solution, the 304 stainless steel tank walls and bottom, and the associated impurities. The composition was irradiated and decayed in the ORIGEN-S case using the history provided in Table 7 above. The first campaign was represented by a 38-hour irradiation followed by 32 days of decay, and so on, through the final 19-hour irradiation representing the tenth campaign.

Page 31 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

Each experiment was assumed to have lasted for 70.5 minutes and to have produced an average thermal power¹¹ of 6.7 mW (the average power and duration reported to ERDA in 1977) (Tuck, 1977, PDF p. 6).¹²

The ORIGEN-S calculation produced time-dependent fission and activation product inventories, with radioactive decay between each of the ten campaigns, for the HEU solution defined in the selected benchmark case, and using the timeline for all uranium solution experiments conducted over the CML's history. Radioactive decay corrections were also applied at the end of the final experiment, using a decay period of 180 days from those specified in ORAUT-OTIB 0054 (2015).

Calculation of Inhalation Intakes and Committed Organ Doses

Solution spills resulting in surface (floor) contamination occurred throughout CML's operating history, as shown in Table 8. Most spills occurred in the late 1960s, but there were also several spills during the 1980s. NIOSH performed organ dose calculations after applying a decay interval of only 180 days to the ending fission and activation product inventory for the HEU solution. This is favorable to the claimant, given that the calculation of the fission and activation product inventory represents the entire operating history of the facility (i.e., includes the period after the last major spill).

¹¹ The power in this context is an average value representing a given number of fissions over a given interval of time because nuclear criticality experiments are not steady-state and are not typically considered in terms of a power level. An average power was used for modeling purposes to account for any change in the composition of the fissile solution (i.e., for depletion effects) and to compute the ingrowth of fission products as the solution was used. In reality, most of the fissions would have occurred near the end of a given experiment when the system was alternately placed in slightly subcritical and slightly supercritical states.

¹² The 6.7 mW value is used, rather than the more precise 3.6 mW for 70.5 minutes estimated by CML staff after the communication with ERDA. There is no indication why 6.7 mW was reported instead of a lower value of 5.4 mW initially calculated by CML staff before refining their estimate. The higher value is adopted as more favorable for claimants.

Page 32 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

Date	Volume (L)	Uranium Mass (kg)	Contaminated Area	PDF Page(s)
7/2/1965	0.5	0.225	22 m ² (Floor)	447
7/14/1965			10 m ² (Floor)	448-449
7/22/1965			Small amount (Floor)	449
11/30/1967		9	(Inside large duct, filter housing, vent line)*	452-462
2/16/1968		1.14**	(Floor and cable trenches)	464-467
5/11/1968	0.06		(Workman's knee)	467
5/9/1969	150.1	16.1	20 m ² (Mixing Room floor)***	467-473
11/25/1980	7	2.66	(Assembly Room hood)	486-487
7/7-20/1984			(Walk-in hood)****	498
2/14/1987			(Personnel, facility and fixtures)*****	500-501
3/13/1987			(Personnel, facility and fixtures)*****	501

Source: Rothe, 2005

*Although contamination was confined to ducts and a filter housing, clean up of this incident resulted in a blowback of dried salts, resulting in facial contamination of a staff member.

**Two conflicting accounts refer to this value as either the solution mass or uranium mass.

***Standing HEU solution covering the floor was cleaned up by a staff member using a critically safe vacuum and wearing plastic booties and a half-face respirator.

****Potentially-contaminated workmen repairing a leaking flange were required to evacuate when a criticality alarm was triggered by an electrician.

*****Two essentially identical events resulted in personnel, fixture, and facility contamination by resuspended high-enriched uranyl nitrate salts accidentally knocked from the surface of a large reactivity shim.

ORAUT-OTIB-0054 (2015) describes a method used to reduce the large number of fission and activation product isotopes in an ORIGEN-S result to a set of 36 dosimetrically significant nuclides. The same 36 nuclides were considered in the inhalation intake and committed organ dose calculations for the CML. Intakes were computed using the 180-day activity values for the HEU solution shown in Table 9, corrected for the average airborne concentration level, and assuming an intake period of 4,000 hours (two working years) at a breathing rate of 1.2 m³/h. The two-year intake period was selected to be consistent with ORAUT-OTIB-0054 (2015), which provides a basis for assigning internal dose from unknown inhalation of fission and activation product mixtures. Radioactive decay of the isotopic mixture over the two-year intake period was not considered, which is favorable to the claimant.

Page 33 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

Activation Products in ONH Fuel at the CML				
Isotope	Activity (Bq)			
Mn-54	1.800E+02			
Fe-55	1.664E+03			
Co-58	1.359E+02			
Co-60	3.077E+00			
Sr-89	1.287E+04			
Sr-90	2.506E+04			
Y-90	2.507E+04			
Y-91	1.984E+04			
Zr-95	2.734E+04			
Nb-95	5.025E+04			
Mo-99	5.206E-14			
Ru-103	4.732E+03			
Ru-106	3.889E+03			
Cd-113m	1.658E+00			
Cd-115m	9.955E-01			
Sb-125	3.236E+02			
Te-129m	1.051E+02			
Te-132	3.937E-11			
I-131	8.936E-02			
I-132	4.055E-11			
Cs-134	7.004E-02			
Cs-136	4.318E-02			
Cs-137	2.567E+04			
Ba-140	3.719E+01			
La-140	4.281E+01			
Ce-141	5.509E+03			
Ce-144	5.417E+04			
Pr-143	6.690E+01			
Pr-144	5.417E+04			
Nd-147	3.204E+00			
Pm-147	2.171E+04			
Pm-148m	0.000E+00			
Sm-151	6.867E+02			

 Table 9: Accumulated Activities of Dosimetrically Significant Fission and

 Activation Products in UNH Fuel at the CML

Page 34 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

Isotope	Activity (Bq)
Eu-154	1.691E-03
Eu-155	3.225E+02
Ta-182	0.000E+00

NOTE: Inventory in the UNH fuel was accumulated without radioactive decay until the final experiment, after which the activities of individual isotopes were decay-corrected for 180 days to yield these values.

Evaluation of air monitoring data in the earlier section, *CML Workplace Air Monitoring*, determined that a weighted-average concentration of 13.5 dpm/m³ for airborne alpha activity was favorable to the claimant. Inhalation intakes were computed by assuming that the airborne alpha activity consisted entirely of HEU having a specific activity of 70 μ Ci/g. Therefore, the airborne mass concentration was 8.7×10^{-8} g/m³ and the total intake over the 4,000-hour period was 4.2×10^{-4} g.

The UNH fuel, as modeled, contained 2,782.8 g HEU. The ratio of total inhalation intake over the two-year intake period and HEU solution mass gives an intake fraction $f = 1.5 \times 10^{-7}$. The inhalation intake *I* for the 36 dosimetrically-significant nuclides for the two-year period was then determined as the product of the ORIGEN-S result for each nuclide after 180 days of decay (activity *A*) and the intake fraction, i.e., I = fA.

Committed organ doses were computed (see Equation 4 below) as the sum of products of the 180-day intakes, computed for each of the 36 dosimetrically significant nuclides, and their corresponding inhalation dose conversion factors (DCF), $e_{inh(50)}$, from ICRP 68 (ICRP, 1995).

$$H(50) = \sum_{i=1}^{36} I_i e_{inh}(50)_i = f \sum_{i=1}^{36} A_i e_{inh}(50)_i$$

The DCFs were partitioned into three solubility categories to account for different absorption types, using the method described in ORAUT-OTIB-0054 (2015). Three committed dose values were therefore computed for each of the 25 individual organs defined in ICRP 68 (ICRP, 1995), corresponding to soluble, moderately soluble, and insoluble materials. Table 10 shows the maximum committed organ dose values for the three solubility categories.

 Table 10: Maximum Committed Organ Doses from Inhalation of Airborne

 Fission and Activation Products at CML

Fission and Activation Froducts at CWL		
Solubility	H(50) (Sv)	Tissue
Soluble (Type F)	$2.5 imes 10^{-9}$	Bone surface
Moderately Soluble (Type M)	$2.3 imes 10^{-9}$	Bone surface
Insoluble (Type S)	$2.4 imes 10^{-9}$	Lung

Page 35 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

These values are greatly reduced over previously calculated committed doses of 3.7×10^{-7} Sv (soluble, bone surface), 4.0×10^{-7} Sv (moderately soluble, lung), and 6.1×10^{-7} Sv (insoluble, lung). Earlier committed doses were calculated using airborne concentrations derived by applying a resuspension factor to the claimant-favorable DOE limit on removable surface contamination. The orders-of-magnitude difference in the two sets of dose values is due to a prior miscalculation in converting from 100 cm² to m². The corrected calculation uses a resuspension factor of 1.5×10^{-4} m⁻¹ and 2,000 dpm/100 cm² removable alpha. This calculation is applied over the entire 220 m² footprint of the CML experimental and material storage areas, giving an estimated air concentration from routine monitoring results, used in calculations for this analysis, further reduces the dose estimate from that obtained previously.

Previous estimates of fission and activation product inventories also assumed a thermal power of 10 mW for 60 minutes, compared with the lesser (but still claimant-favorable) value of 6.7 mW for 70.5 minutes used in this analysis to describe conditions for the typical CML criticality experiment.

SUMMARY AND CONCLUSIONS

Re-evaluation of unmonitored personnel dose using recently captured air monitoring data and reactor performance estimates for the Rocky Flats Plant Critical Mass Laboratory has resulted in estimates on the order of a few nanosieverts for maximum organ doses due to inhalation of resuspended contamination containing mixed fission and activation products. These estimates are over two orders of magnitude lower than previous estimates. The greatest contributor to the large reduction in estimated doses is a correction in the calculation of a conversion factor. Lesser contributors to the reduction are lower estimates of reactor power in a typical criticality experiment at CML, and a lower value for respirable alpha air concentrations based on routine air monitoring results.

NIOSH computer-modeled criticality experiments using estimates of typical reactor power and corresponding neutron flux documented by CML research staff and alpha air concentrations from routine monitoring results. Based on its modeling, NIOSH concludes that no significant personnel dose to Rocky Flats workers or contractors resulted from the generation of fission or activation products in the uranyl nitrate fuel or resuspended contamination from fuel spills as a result of criticality experiments conducted at CML over its lifetime.

Page 36 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

REFERENCES

Air Samples, 1980, *Air Samples Buildings 883 and 886*; Rocky Flats Plant; December 1980; SRDB Ref ID: 159122

Air Samples, 1981a, *Air Samples Building* 875; Rocky Flats Plant; January 1981; SRDB Ref ID: 159124

Air Samples, 1981b, *Air Samples Building* 875; Rocky Flats Plant; December 1981; SRDB Ref ID: 159125

Air Samples, 1982a, *Air Samples Building* 875; Rocky Flats Plant; January 1982; SRDB Ref ID: 159126

Air Samples, 1982b, *Air Samples Building 875*; Rocky Flats Plant; February 1982; SRDB Ref ID: 159127

Air Samples, 1982c, *Air Samples Building* 875; Rocky Flats Plant; March 1982; SRDB Ref ID: 159128

Air Samples, 1982d, *Air Samples Building 875*; Rocky Flats Plant; April 1982; SRDB Ref ID: 159129

Air Samples, 1982e, *Air Samples Building* 875; Rocky Flats Plant; May 1982; SRDB Ref ID: 159130

Air Samples, 1982f, *Air Samples Building 875*; Rocky Flats Plant; June 1982; SRDB Ref ID: 159131

Air Samples, 1982g, *Air Samples Building* 875; Rocky Flats Plant; July 1982; SRDB Ref ID: 159132

Air Samples, 1982h, *Air Samples Building 875*; Rocky Flats Plant; August 1982; SRDB Ref ID: 159133

Air Samples, 1982i, *Air Samples Building 875*; Rocky Flats Plant; November 1982; SRDB Ref ID: 159135

Air Samples, 1983a, *Air Samples Building 875*; Rocky Flats Plant; May 1983; SRDB Ref ID: 159137

Air Samples, 1983b, *Air Samples Building* 875; Rocky Flats Plant; June 1983; SRDB Ref ID: 159138

Page 37 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

Air Samples, 1983c, Air Samples Buildings 865 and 886; Rocky Flats Plant; May 1983; SRDB Ref ID: 159136

Air Samples, 1983d, *Air Samples Buildings 865 and 886*; Rocky Flats Plant; September 1983; SRDB Ref ID: 159154

Air Samples, 1983e, Air Filter Direct Alpha Counting System Buildings 865 and 886; Rocky Flats Plant; October 1983; SRDB Ref ID: 156834

Air Samples, 1984a, *Air Samples Building* 875; Rocky Flats Plant; January 1984; SRDB Ref ID: 159155

Air Samples, 1984b, *Air Samples Building 875*; Rocky Flats Plant; April 1984; SRDB Ref ID: 159158

Air Samples, 1984c, *Air Samples Building* 875; Rocky Flats Plant; May 1984; SRDB Ref ID: 159160

Air Samples, 1984d, *Air Samples Building* 875; Rocky Flats Plant; June 1984; SRDB Ref ID: 159162

Air Samples, 1984e, *Air Sample Direct Alpha Counting System Buildings 865 and 886*; Rocky Flats Plant; July 1984; SRDB Ref ID: 156857

Air Samples, 1984f, *Air Sample Direct Alpha Counting System Buildings 865 and 886*; Rocky Flats Plant; August 1984; SRDB Ref ID: 156858

Air Samples, 1984g, *Air Sample Direct Alpha Counting System Buildings 865 and 886*; Rocky Flats Plant; September 1984; SRDB Ref ID: 156859

Air Samples, 1984h, *Air Sample Direct Alpha Counting System Buildings 865 and 886*; Rocky Flats Plant; October 1984; SRDB Ref ID: 156860

Air Samples, 1984i, *Air Sample Direct Alpha Counting System Buildings 865 and 886*; Rocky Flats Plant; November 1984; SRDB Ref ID: 156861

Air Samples, 1984j, *Air Sample Direct Alpha Counting System Buildings 865 and 886*; Rocky Flats Plant; December 1984; SRDB Ref ID: 156862

Air Samples, 1985a, *Air Filter Direct Alpha Counting System Building* 875; Rocky Flats Plant; January 1985; SRDB Ref ID: 156864

Air Samples, 1985b, *Air Filter Direct Alpha Counting System Building 875*; Rocky Flats Plant; February 1985; SRDB Ref ID: 156875

Page 38 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

Air Samples, 1985c, *Air Filter Direct Alpha Counting System Building 875*; Rocky Flats Plant; March 1985; SRDB Ref ID: 156877

Air Samples, 1985d, *Air Filter Direct Alpha Counting System Building 875*; Rocky Flats Plant; April 1985; SRDB Ref ID: 156879

Air Samples, 1985e, *Air Samples Building* 875; Rocky Flats Plant; December 1985; SRDB Ref ID: 159139

Air Samples, 1985f, *Air Sample Direct Alpha Counting System Buildings 865 and 886*; Rocky Flats Plant; January 1985; SRDB Ref ID: 156863

Air Samples, 1985g, Air Sample Direct Alpha Counting System Buildings 865 and 886; Rocky Flats Plant; February 1985; SRDB Ref ID: 156867

Air Samples, 1985h, *Air Sample Direct Alpha Counting System Buildings 865 and 886*; Rocky Flats Plant; Mar 1985; SRDB Ref ID: 156876

Air Samples, 1985i, *Air Sample Direct Alpha Counting System Buildings 865 and 886*; Rocky Flats Plant; April 1985; SRDB Ref ID: 156878

Air Samples, 1985j, *Air Samples Direct Alpha Counting System Building 865 and 886*; Rocky Flats Plant; May 1985; SRDB Ref ID: 160323

Air Samples, 1985k, Air Samples Buildings 865 and 886; Rocky Flats Plant; June 1985; SRDB Ref ID: 159142

Air Samples, 1985l, *Air Samples Buildings 865 and 886*; Rocky Flats Plant; July 1985; SRDB Ref ID: 159143

Air Samples, 1985m, *Air Samples Buildings 865 and 886*; Rocky Flats Plant; August 1985; SRDB Ref ID: 159144

Air Samples, 1985n, *Air Samples Buildings 865 and 886*; Rocky Flats Plant; September 1985; SRDB Ref ID: 159145

Air Samples, 19850, *Air Samples Buildings 865 and 886*; Rocky Flats Plant; October 1985; SRDB Ref ID: 159146

Air Samples, 1985p, *Air Samples Buildings 865 and 886*; Rocky Flats Plant; November 1985; SRDB Ref ID: 159147

Air Samples, 1985q, *Air Samples Buildings 865 and 886*; Rocky Flats Plant; December 1985; SRDB Ref ID: 159148

Page 39 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

Air Samples, 1986a, *Air Filter Direct Alpha Counting System Building* 875; Rocky Flats Plant; January 1986; SRDB Ref ID: 156881

Air Samples, 1986b, *Air Filter Direct Alpha Counting System Building 875*; Rocky Flats Plant; February 1986; SRDB Ref ID: 156883

Air Samples, 1986c, *Air Filter Direct Alpha Counting System Building* 875; Rocky Flats Plant; March 1986; SRDB Ref ID: 156884

Air Samples, 1986d, *Air Filter Direct Alpha Counting System Building 875*; Rocky Flats Plant; April 1986; SRDB Ref ID: 156885

Air Samples, 1986e, *Air Filter Direct Alpha Counting System Building* 875; Rocky Flats Plant; May 1986; SRDB Ref ID: 156886;

Air Samples, 1986f, *Air Filter Direct Alpha Counting System Building* 875; Rocky Flats Plant; June 1986; SRDB Ref ID: 156888

Air Samples, 1986g, *Air Filter Direct Alpha Counting System Building* 875; Rocky Flats Plant; July 1986; SRDB Ref ID: 156890

Air Samples, 1986h, *Air Filter Direct Alpha Counting System Building* 875; Rocky Flats Plant; August 1986; SRDB Ref ID: 156891

Air Samples, 1986i, *Air Filter Direct Alpha Counting System Building* 875; Rocky Flats Plant; September 1986; SRDB Ref ID: 156892

Air Samples, 1986j, *Air Sample Travel Logs Building 886 Using Ludium 12*; Rocky Flats Plant; September 24-26, 1986; SRDB Ref ID: 156893

Air Samples, 1986k, *Air Filter Direct Alpha Counting System Building 875*; Rocky Flats Plant; October 1986; SRDB Ref ID: 156894

Air Samples, 1986l, *Air Filter Direct Alpha Counting System Building* 875; Rocky Flats Plant; November 1986; SRDB Ref ID: 156895

Air Samples, 1986m, *Air Filter Direct Alpha Counting System Building* 875; Rocky Flats Plant; December 1986; SRDB Ref ID: 156897

Air Samples, 1986n, *Air Sample Direct Alpha Counting System Building 865 and 886*; Rocky Flats Plant; January 1986; SRDB Ref ID: 156880

Air Samples, 1986o, *Air Sample Direct Alpha Counting System Building 865 and 886*; Rocky Flats Plant; February 1986; SRDB Ref ID: 156882

Page 40 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

Air Samples, 1986p, *Air Sample Direct Alpha Counting System Building 865 and 886*; Rocky Flats Plant; June 1986; SRDB Ref ID: 156887

Air Samples, 1986q, *Air Sample Direct Alpha Counting System Building 865 and 886*; Rocky Flats Plant; July 1986; SRDB Ref ID: 156889

Air Samples, 1986r, *Air Samples Direct Alpha Counting System Building 865 and 886*; Rocky Flats Plant; November 1986; SRDB Ref ID: 160325

Air Samples, 1986s, *Air Sample Direct Alpha Counting System Building 865 and 886*; Rocky Flats Plant; December 1986; SRDB Ref ID: 156896

Air Samples, 1987a, *Air Samples Building* 875; Rocky Flats Plant; January 1987; SRDB Ref ID: 159140

Air Samples, 1987b, *Air Samples Buildings 865 and 886*; Rocky Flats Plant; January 1987; SRDB Ref ID: 159149

Air Samples, 1987c, *Air Samples Building 886*; Rocky Flats Plant; February 1987; SRDB Ref ID: 159123

Air Samples, 1987d, *Air Samples Building 886*; Rocky Flats Plant; Mar 1987; SRDB Ref ID: 159150

Air Samples, 1987e, *Air Samples Building* 886; Rocky Flats Plant; May 1987; SRDB Ref ID: 159151

Air Samples, 1987f, *Air Samples Building* 886; Rocky Flats Plant; July 1987; SRDB Ref ID: 159152

Air Samples, 1987g, *Air Samples Building* 886; Rocky Flats Plant; August 1987; SRDB Ref ID: 159153

Air Samples, 1987h, *Air Samples Building* 886; Rocky Flats Plant; September 1987; SRDB Ref ID: 159156

Air Samples, 1987i, *Air Samples Building* 886; Rocky Flats Plant; December 1987; SRDB Ref ID: 159157

Air Samples, 1988a, *Effluent Air Survey Building* 875; Rocky Flats Plant; May 1988; SRDB Ref ID: 156898

Air Samples, 1988b, *Air Filter Direct Alpha Counting System Building* 875; Rocky Flats Plant; January 1988; SRDB Ref ID: 156899

Page 41 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

Air Samples, 1988c, *Air Filter Direct Alpha Counting System Building* 875; Rocky Flats Plant; February 1988; SRDB Ref ID: 156901

Air Samples, 1988d, Air Filter Direct Alpha Counting System Building 875; Rocky Flats Plant; March 1988; SRDB Ref ID: 156903

Air Samples, 1988e, *Air Filter Direct Alpha Counting System Building* 875; Rocky Flats Plant; April 1988; SRDB Ref ID: 156905

Air Samples, 1988f, *Air Filter Direct Alpha Counting System Building* 875; Rocky Flats Plant; May 1988; SRDB Ref ID: 156906

Air Samples, 1988g, *Air Samples Building 875*; Rocky Flats Plant; September 1988; SRDB Ref ID: 159141

Air Samples, 1988h, *Air Sample Direct Alpha Counting System Building 886*; Rocky Flats Plant; January 1988; SRDB Ref ID: 156900

Air Samples, 1988i, *Air Sample Direct Alpha Counting System Building 886*; Rocky Flats Plant; February 1988; SRDB Ref ID: 156902

Air Samples, 1988j, *Air Sample Direct Alpha Counting System Building 886*; Rocky Flats Plant; April 1988; SRDB Ref ID: 156907

Air Samples, 1988k, *Air Samples Building 886*; Rocky Flats Plant; November 1988; SRDB Ref ID: 159159

Air Samples, 1988, *Air Samples Building 886*; Rocky Flats Plant; November 1988; SRDB Ref ID: 159161

Air Samples, 1989, *Air Samples Building 886*; Rocky Flats Plant; June 1989; SRDB Ref ID: 159163

Analysis Report; August 7, 1977; SRDB Ref ID: 157754

Building 886, 2011, Rocky Flats Plant, Critical Mass Laboratory, HAER No. CO-83-A (Rocky Flats Plant, Building 886); U.S. Department of Energy, Legacy Management, Historic American Engineering Record, Rocky Flats Site, Building 886; November 3, 2011; SRDB Ref ID: 104452

Calibrations, 1987, *Building 886 and 875 Airhead Calibrations*; Rocky Flats Plant; January-April, July-August, and October 1987; SRDB Ref ID: 152336

Calibrations, 1988, *Building 886 and 875 Airhead Calibrations*; Rocky Flats Plant; January, March, and August-September 1988; SRDB Ref ID: 152339

Page 42 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

Calibrations, 1989a, *Building 886 and 875 Airhead and SAAM Calibrations*; Rocky Flats Plant; January, February, and April 1989; SRDB Ref ID: 152512

Calibrations, 1989b, *Building 886 and 875 Airhead Calibrations*; Rocky Flats Plant; May-August 1989; SRDB Ref ID: 152513

DOE (U.S. Department of Energy), 2011, *Historic American Engineering Record Rocky Flats Site Building 865 Metal Research and Development Laboratory*; U.S. Department of Energy Legacy Management; November 28, 2011; SRDB Ref ID: 105198

Experiment Run 2-8-170; Undated; SRDB Ref ID: 157750

Experiments at RFNSF, 1965 to April 19, 1977, 1977a; April 19, 1977; SRDB Ref ID: 157752

Experiments at RFNSF, 1965 to April 19, 1977, 1977b; April 19, 1977; SRDB Ref ID: 157757

ICRP (International Commission on Radiological Protection), 1995, *Dose Coefficients for Intakes of Radionuclides by Workers*; ICRP Publication 68; Oxford, New York: Pergamon Press; 1995; SRDB Ref ID: 22731

Introducing Nuclear Reactor Theory and Experiments 2-8-169 and 2-8-170; May 4, 1977; SRDB Ref ID: 157748

Log, 1967, *Console Log #3, January 3 and 6, 1967*; Rocky Flats Plant; January 3 and 6, 1967; SRDB Ref ID: 157753

Log, 1976, *Building 886 Fission Due to Experiment Gamma Level Oy Shells*, Rocky Flats Plant; April 29, 1976; SRDB Ref ID: 157751

NIOSH, 2006, SEC Petition Evaluation Report for Petition SEC-00030, Rocky Flats Plant; National Institute for Occupational Safety and Health (NIOSH); April 7, 2006; SRDB Ref ID: 132776

ORAUT-OTIB-0004, *Estimating the Maximum Plausible Dose to Workers at Atomic Weapons Employer Facilities*, Revision 3, PC-2; ORAU Team Dose Reconstruction Project for NIOSH; December 6, 2006; SRDB Ref ID: 36191

ORAUT-OTIB-0054, Fission and Activation Product Assignment for Internal Dose-Related Gross Beta and Gross Gamma Analyses, Revision 3; ORAU Team Dose Reconstruction Project for NIOSH; February 6, 2015; SRDB Ref ID: 315479

Palmer, 2004, "Minimally Reflected Cylinders of Highly Enriched Solutions of Uranyl Nitrate;" NEA/NSC/DOC(95)03/II, Volume II; HEU-SOL-THERM-001, from the *International Handbook of Evaluated Criticality Safety Benchmark Experiments*; Brian Palmer, Idaho Chemical Processing Plant; September 30, 2004; SRDB Ref ID: 142464

Page 43 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

Personal Communication, 2015a, *Personal Communication with former Rocky Flats Worker*; telephone interview ORAU Team, ABRWH, DCAS, and Advocates; October 13, 2015; SRDB Ref ID: 150603

Personal Communication, 2015b, *Personal Communication with former Rocky Flats Worker*; telephone interview ORAU Team and DCAS; October 13, 2015; SRDB Ref ID: 150602

Radiation Monitoring Technical Support Programs, 1976, *Supplied Breathing Air Procedures Radiation Monitoring and Routine Air Sampling Procedures*; HS-RM4.1; Rocky Flats Plant; March 1976; SRDB Ref ID: 24235

Radiological Surveys, 1980a, *Daily Control Point, Dry Swipe, Gamma and Neutron and Radiation Monitoring Surveys Building 886*; Rocky Flats Plant; January 1980; SRDB Ref ID: 156807

Radiological Surveys, 1980b, *Daily Control Point, Dry Swipe and Gamma Neutron Surveys Buildings* 875 and 886; Rocky Flats Plant; February 1980; SRDB Ref ID: 156808

Radiological Surveys, 1980c, *Daily Control Point, Dry Swipe, Gamma Neutron and Radiation Monitoring Survey Results Buildings 886 and 875*; Rocky Flats Plant; March 1980; SRDB Ref ID: 156809

Radiological Surveys, 1980d, *Daily Control Point, Dry Swipe and Gamma Neutron Surveys Buildings* 875 and 886; Rocky Flats Plant; April 1980; SRDB Ref ID: 156810

Radiological Surveys, 1980e, *Daily Control Point and Dry Swipe Surveys Buildings 875 and 886*; Rocky Flats Plant; May 1980; SRDB Ref ID: 156811

Radiological Surveys, 1980f, *Daily Control Point and Dry Swipe Surveys Buildings 875 and 886*; Rocky Flats Plant; June 1980; SRDB Ref ID: 156812

Radiological Surveys, 1980g, *Daily Control Point, Dry Swipe, Gamma Neutron and Radiation Monitoring Surveys Buildings 875 and 886*; Rocky Flats Plant; July 1980; SRDB Ref ID: 156813

Radiological Surveys, 1980h, *Daily Control Point, Dry Swipe and Gamma Neutron Surveys Building 886*; Rocky Flats Plant; August 1980; SRDB Ref ID: 156814

Radiological Surveys, 1980i, *Daily Control Point, Dry Swipe and Gamma Neutron Surveys Building 886*; Rocky Flats Plant; September 1980; SRDB Ref ID: 156815

Radiological Surveys, 1980j, *Daily Control Point, Dry Swipe and Gamma Neutron Surveys Building 886*; Rocky Flats Plant; October 1980; SRDB Ref ID: 156816

Radiological Surveys, 1980k, *Daily Control Point, Dry Swipe and Gamma Neutron Surveys Building 886*; Rocky Flats Plant; November 1980; SRDB Ref ID: 156817

Page 44 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

Radiological Surveys, 1980l, *Daily Control Point, Dry Swipe and Gamma Neutron Surveys Building 875 and 886*; Rocky Flats Plant; December 1980; SRDB Ref ID: 156818

Radiological Surveys, 1981a, *Building 886 Radiological Surveys*; Rocky Flats Plant; October 1981; SRDB Ref ID: 152233

Radiological Surveys, 1981b, *Building 886 Radiological Surveys*; Rocky Flats Plant; November 1981; SRDB Ref ID: 152245

Radiological Surveys, 1981c, *Building 886 Radiological Surveys*; Rocky Flats Plant; January 1981; SRDB Ref ID: 152247

Radiological Surveys, 1981d, *Building 886 Radiological Surveys*; Rocky Flats Plant; December 1981; SRDB Ref ID: 152248

Radiological Surveys, 1981e, *Building 886 Radiological Surveys*; Rocky Flats Plant; February 1981; SRDB Ref ID: 152250

Radiological Surveys, 1981f, *Building 886 Radiological Surveys*; Rocky Flats Plant; March 1981; SRDB Ref ID: 152251

Radiological Surveys, 1981g, *Building 886 Radiological Surveys*; Rocky Flats Plant; April 1981; SRDB Ref ID: 152253

Radiological Surveys, 1981h, *Building 886 Radiological Surveys*; Rocky Flats Plant; May 1981; SRDB Ref ID: 152255

Radiological Surveys, 1981i, *Building 886 Radiological Surveys*; Rocky Flats Plant; June 1981; SRDB Ref ID: 152257

Radiological Surveys, 1981j, *Building 886 Radiological Surveys*; Rocky Flats Plant; July 1981; SRDB Ref ID: 152259

Radiological Surveys, 1981k, *Building 886 Radiological Surveys*; Rocky Flats Plant; August 1981; SRDB Ref ID: 152261

Radiological Surveys, 19811, *Building 875 Radiological Surveys*; Rocky Flats Plant; September 1981; SRDB Ref ID: 152262

Radiological Surveys, 1981m, *Building 886 Radiological Surveys*; Rocky Flats Plant; September 1981; SRDB Ref ID: 152263

Radiological Surveys, 1982a, *Building 886 Radiological Surveys*; Rocky Flats Plant; July 1982; SRDB Ref ID: 152264

Page 45 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

Radiological Surveys, 1982b, *Building 886 Radiological Surveys*; Rocky Flats Plant; August 1982; SRDB Ref ID: 152266

Radiological Surveys, 1982c, *Building 886 Radiological Surveys*; Rocky Flats Plant; September 1982; SRDB Ref ID: 152267

Radiological Surveys, 1982d, *Building 886 Radiological Surveys*; Rocky Flats Plant; October 1982; SRDB Ref ID: 152268

Radiological Surveys, 1982e, *Building 886 Radiological Surveys*; Rocky Flats Plant; November 1982; SRDB Ref ID: 152269

Radiological Surveys, 1982f, *Building 886 Radiological Surveys*; Rocky Flats Plant; December 1982; SRDB Ref ID: 152270

Radiological Surveys, 1982g, *Building 886 Radiological Surveys*; Rocky Flats Plant; February 1982; SRDB Ref ID: 152276

Radiological Surveys, 1982h, *Building 886 Radiological Surveys*; Rocky Flats Plant; March 1982; SRDB Ref ID: 152281

Radiological Surveys, 1982i, *Building 886 Radiological Surveys*; Rocky Flats Plant; April 1982; SRDB Ref ID: 152288

Radiological Surveys, 1982j, *Building 886 Radiological Surveys*; Rocky Flats Plant; May 1982; SRDB Ref ID: 152292

Radiological Surveys, 1982k, *Building 886 Radiological Surveys with Survey of Sr-90 Sulfate Containers*; Rocky Flats Plant; June 1982; SRDB Ref ID: 152295

Radiological Surveys, 19821, *Floor, Daily Control and Gamma Neutron Dry Swipe Surveys Building 886*; Rocky Flats Plant; January 1982; SRDB Ref ID: 156820

Radiological Surveys, 1983a, *Building 886 Radiological Surveys*; Rocky Flats Plant; November 1983; SRDB Ref ID: 152271

Radiological Surveys, 1983b, *Building 886 Radiological Surveys*; Rocky Flats Plant; December 1983; SRDB Ref ID: 152272

Radiological Surveys, 1983c, *Daily and Monthly Control Point, Controlled Access Area and Offices Dry Swipe Results Building* 886; Rocky Flats Plant; January 1983; SRDB Ref ID: 156822

Page 46 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

Radiological Surveys, 1983d, *Daily, Weekly and Monthly Control Point, Controlled Access Area and Offices Dry Swipe Results Building 886*; Rocky Flats Plant; February 1983; SRDB Ref ID: 156824

Radiological Surveys, 1983e, *Daily, Weekly and Monthly Control Point, Controlled Access Area and Offices Dry Swipe Results Building 886*; Rocky Flats Plant; March 1983; SRDB Ref ID: 156825

Radiological Surveys, 1983f, *Daily and Monthly Control Point, Controlled Access Area and Offices Dry Swipe Results Building 886*; Rocky Flats Plant; April 1983; SRDB Ref ID: 156826

Radiological Surveys, 1983g, *Contamination Surveys Building 886*; Rocky Flats Plant; June 1983; SRDB Ref ID: 159203

Radiological Surveys, 1983h, *Contamination Surveys Building* 886; Rocky Flats Plant; July 1983; SRDB Ref ID: 159204

Radiological Surveys, 1983i, *Contamination Surveys Building* 886; Rocky Flats Plant; August 1983; SRDB Ref ID: 159205

Radiological Surveys, 1983j, *Contamination Surveys Building 886*; Rocky Flats Plant; September 1983; SRDB Ref ID: 159207

Radiological Surveys, 1983k, *Contamination Surveys Building* 886; Rocky Flats Plant; October 1983; SRDB Ref ID: 159210

Radiological Surveys, 1984a, *Building 875 Radiological Surveys*; Rocky Flats Plant; October, 1984; SRDB Ref ID: 152229

Radiological Surveys, 1984b, *Building 886 Radiological Surveys*; Rocky Flats Plant; January 1984; SRDB Ref ID: 152273

Radiological Surveys, 1984c, *Building 886 Radiological Surveys*; Rocky Flats Plant; February 1984; SRDB Ref ID: 152277

Radiological Surveys, 1984d, *Building 886 Radiological Surveys*; Rocky Flats Plant; March 1984; SRDB Ref ID: 152280

Radiological Surveys, 1984e, *Building 886 Radiological Surveys*; Rocky Flats Plant; April 1984; SRDB Ref ID: 152284

Radiological Surveys, 1984f, *Building 886 Radiological Surveys*; Rocky Flats Plant; May 1984; SRDB Ref ID: 152286

Page 47 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

Radiological Surveys, 1984g, *Building 886 Radiological Surveys*; Rocky Flats Plant; June 1984; SRDB Ref ID: 152289

Radiological Surveys, 1984h, *Building 886 Radiological Surveys*; Rocky Flats Plant; July 1984; SRDB Ref ID: 152293

Radiological Surveys, 1984i, *Building 886 Radiological Surveys*; Rocky Flats Plant; August 1984; SRDB Ref ID: 152299

Radiological Surveys, 1984j, *Building 886 Radiological Surveys*; Rocky Flats Plant; September 1984; SRDB Ref ID: 152301

Radiological Surveys, 1984k, *Building 886 Radiological Surveys*; Rocky Flats Plant; October 1984; SRDB Ref ID: 152302

Radiological Surveys, 1984l, *Building 886 Radiological Surveys*; Rocky Flats Plant; November 1984; SRDB Ref ID: 152304

Radiological Surveys, 1984m, *Building 886 Radiological Surveys*; Rocky Flats Plant; December 1984; SRDB Ref ID: 152318

Radiological Surveys, 1985a, *Building 886 Radiological Surveys*; Rocky Flats Plant; January 1985; SRDB Ref ID: 152323

Radiological Surveys, 1985b, *Building 886 Radiological Surveys*; Rocky Flats Plant; February 1985; SRDB Ref ID: 152325

Radiological Surveys, 1985c, *Building 886 Radiological Surveys*; Rocky Flats Plant; March 1985; SRDB Ref ID: 152331

Radiological Surveys, 1985d, *Building 886 Radiological Surveys*; Rocky Flats Plant; April 1985; SRDB Ref ID: 152335

Radiological Surveys, 1985e, *Building 886 Radiological Surveys*; Rocky Flats Plant; May 1985; SRDB Ref ID: 152340

Radiological Surveys, 1985f, *Building 875 Radiological Surveys*; Rocky Flats Plant; June 1985; SRDB Ref ID: 152342

Radiological Surveys, 1985g, *Building 886 Radiological Surveys*; Rocky Flats Plant; June 1985; SRDB Ref ID: 152343

Radiological Surveys, 1985h, *Building 886 Radiological Surveys*; Rocky Flats Plant; July 1985; SRDB Ref ID: 152344

Page 48 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

Radiological Surveys, 1985i, *Building 886 Radiological Surveys*; Rocky Flats Plant; August 1985; SRDB Ref ID: 152346

Radiological Surveys, 1985j, *Radiation Monitoring Surveys, Weekly, Monthly, Control Points and Dry Swipe Results Buildings 886, 875, and 880*; Rocky Flats Plant; September 1985; SRDB Ref ID: 157168

Radiological Surveys, 1985k, *Radiation Monitoring Surveys, Weekly, Monthly, Control Points and Dry Swipe Results Buildings* 886, 875, and 880; Rocky Flats Plant; October 1985; SRDB Ref ID: 157170

Radiological Surveys, 19851, *Radiation Monitoring Surveys, Weekly, Monthly, Control Points, Gamma Neutron Surveys and Dry Wipe Results Buildings* 886, 875, and 880; Rocky Flats Plant; November 1985; SRDB Ref ID: 157172

Radiological Surveys, 1985m, *Radiation Monitoring Surveys, Weekly, Monthly, Control Points and Dry Swipe Results Buildings 886, 875, and 880*; Rocky Flats Plant; December 1985; SRDB Ref ID: 157173

Radiological Surveys, 1986a, *Building 886 Radiological Surveys*; Rocky Flats Plant; April 1986; SRDB Ref ID: 152298

Radiological Surveys, 1986b, *Building 886 Radiological Surveys*; Rocky Flats Plant; May 1986; SRDB Ref ID: 152306

Radiological Surveys, 1986c, *Building 886 Radiological Surveys*; Rocky Flats Plant; June 1986; SRDB Ref ID: 152308

Radiological Surveys, 1986d, *Building 886 Radiological Surveys*; Rocky Flats Plant; July 1986; SRDB Ref ID: 152310

Radiological Surveys, 1986e, *Building 886 Radiological Surveys*; Rocky Flats Plant; August 1986; SRDB Ref ID: 152312

Radiological Surveys, 1986f, *Building 886 Radiological Surveys*; Rocky Flats Plant; September 1986; SRDB Ref ID: 152314

Radiological Surveys, 1986g, *Building 886 Radiological Surveys*; Rocky Flats Plant; September-October 1986; SRDB Ref ID: 152317

Radiological Surveys, 1986h, *Building 886 Radiological Surveys*; Rocky Flats Plant; November 1986; SRDB Ref ID: 152320

Radiological Surveys, 1986i, *Building 886 Radiological Surveys*; Rocky Flats Plant; December 1986; SRDB Ref ID: 152326

Page 49 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

Radiological Surveys, 1986j, *Building 886 Radiological Surveys*; Rocky Flats Plant; January 1986; SRDB Ref ID: 152351

Radiological Surveys, 1986k, *Building 886 Radiological Surveys*; Rocky Flats Plant; February 1986; SRDB Ref ID: 152353

Radiological Surveys, 1986l, *Building 886 Radiological Surveys*; Rocky Flats Plant; March 1986; SRDB Ref ID: 152355

Radiological Surveys, 1987a, *Building 886 Cold Area Radiological Surveys*; Rocky Flats Plant; 1987; SRDB Ref ID: 152327

Radiological Surveys, 1987b, *Building 886 Control Point Radiological Surveys*; Rocky Flats Plant; 1987; SRDB Ref ID: 152328

Radiological Surveys, 1987c, *Building 886 Dry Alpha Sweep Radiological Surveys*; Rocky Flats Plant; 1987; SRDB Ref ID: 152329

Radiological Surveys, 1987d, *Building 886 Neutron-Photon Radiological Surveys*; Rocky Flats Plant; 1987; SRDB Ref ID: 152330

Radiological Surveys, 1987e, *Building 886 Equipment Release Survey*; Rocky Flats Plant; June 1987; SRDB Ref ID: 152332

Radiological Surveys, 1988a, *Buildings 886 and 875 SAAM Alarm Log Sheets*; Rocky Flats Plant; April-May 1988; SRDB Ref ID: 152341

Radiological Surveys, 1988b, *Building 886 Cold Area Radiological Surveys*; Rocky Flats Plant; January-November 1988; SRDB Ref ID: 152348

Radiological Surveys, 1988c, *Building 886 Control Point Radiological Surveys*; Rocky Flats Plant; January-November 1988; SRDB Ref ID: 152357

Radiological Surveys, 1988d, *Building 886 Dry Swipe Radiological Surveys*; Rocky Flats Plant; January-October 1988; SRDB Ref ID: 152359

Radiological Surveys, 1988e, *Building 886 Neutron-Photon Radiological Surveys*; Rocky Flats Plant; February and August-September 1988; SRDB Ref ID: 152360

Radiological Surveys, 1989a, *Building 886 Cold Area Radiological Surveys*; Rocky Flats Plant; January-April 1989; SRDB Ref ID: 152362

Radiological Surveys, 1989b, *Building 886 Contamination Surveys*; Rocky Flats Plant; January-June and October-December 1989; SRDB Ref ID: 152500

Page 50 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.

Radiological Surveys, 1989c, *Building 886 Control Point Radiological Surveys*; Rocky Flats Plant; January October 1989; SRDB Ref ID: 152502

Radiological Surveys, 1989d, *Building 886 Neutron-Photon Radiological Surveys*; Rocky Flats Plant; January-November 1989; SRDB Ref ID: 152507

Radiological Surveys, 1989e, *Building 886 Radiological Surveys*; Rocky Flats Plant; May-November 1989; SRDB Ref ID: 152508

Radiological Surveys, 1989f, *Building 886 Office Area Surveys*; Rocky Flats Plant; April-October 1989; SRDB Ref ID: 152509

Radiological Surveys, 1989g, *Building 886 Smear Counter Performance Tests*; Rocky Flats Plant; December 1989; SRDB Ref ID: 152511

Radiological Surveys, 1990a, *Building 886 Contamination Surveys*; Rocky Flats Plant; January-June and October-December1990; SRDB Ref ID: 152515

Radiological Surveys, 1990b, Building 886 Gamma and Neutron-Photon Surveys; Rocky Flats Plant; January-July and September-December 1990; SRDB Ref ID: 152516

Rothe, 2005, A Technically Useful History of the Critical Mass Laboratory at Rocky Flats, LA-UR-05-3247, R. E. Rothe; Los Alamos National Laboratory; May 2005; SRDB Ref ID: 21358

Summary of All Nuclear Safety Experiments; April 19, 1977; SRDB Ref ID: 157749

Tuck, 1977, Total Fissions Produced by Critical Approach Experiments Done at the Rocky Flats Plant Nuclear Facility from September 1965 to June 1, 1977; Grover Tuck, Rocky Flats Nuclear Safety Facility; June 3, 1977; SRDB Ref ID: 157872

Page 51 of 51

This is a working document prepared by NIOSH's Division of Compensation Analysis and Support (DCAS) or its contractor for use in discussions with the ABRWH or its Working Groups or Subcommittees. Draft, preliminary, interim, and White Paper documents are not final NIOSH or ABRWH (or their technical support and review contractors) positions unless specifically marked as such. This document represents preliminary positions taken on technical issues prepared by NIOSH or its contractor. **NOTICE: This report has been reviewed to identify and redact any information that is protected by the** <u>Privacy Act 5 USC §552a</u> and has been cleared for distribution.